

**METHOD OF CONDUCTING A STATE-WIDE
HIGHWAY PLANNING SURVEY**

A Thesis

**Submitted for the Degree of
CIVIL ENGINEER**

By

Herbert Reinhold Jacobson

B. S. in C. E., 1932

Georgia School of Technology

Approved by:

W. J. O.

June 1, 1938

INDEX OF THESIS

	Page
PART I The Necessity of Highway Planning	1
PART II The Purpose of a Highway Planning Survey	5
PART III Road Inventory - Field Work	8
General	8
Odometer	9
Triangulation and Traverse Stations	10
Federal and State Projects	10
Cities and Towns	10
Reservations	11
Roads	12
Culverts	13
Bridges - General	13
Draw Bridges	15
Toll Bridges	15
Ferries	15
Railroad Crossings	16
Cultural Items with Symbols	16
Road Classification	19
Sample Forms HPS-1, 4, 5, 6, 8, and 200	24
Road Inventory - Drafting	25
Map Series	25
Drafting Proceedure	29
Sample Form HPS-8 (Method of Adjustment)	31
Plate Showing Standard Symbols	31
Sample Maps	31

Sight Distance Survey	32
General	32
Survey Proceedure	33
Drawing of Equipment used on Sight Distance Survey	34
Sample of Sight Distance Notes	34
Horizontal Curvature Survey	35
General	35
Curvature Protractor	35
Survey Proceedure	37
Drawing of Equipment used on Horizontal Curvature Survey	37
Sample of Curvature Notes	37
 PART IV	
Traffic Survey - Density Data	38
General	38
Key Stations	39
Computation of Twenty-four Hour Annual Average	42
Sample Table of Computed Annual Count	45
Sample Traffic Flow Map	45
Blanket Count Stations	46
Origin-Destination Study	47
Automatic Counters	49
Installation Sketch for Automatic Counters	50
Traffic Survey - Weight Data	51
Loadometer Stations	51
Sketch Map of Key and Loadometer Stations	55
Pit Scale Stations	56

	Sample Forms HPS T-11, 15, 17, 18, 19, 20a, 20b, 24, 25, 26	59
PART V	Financial Survey	60
	Fiscal Survey	60
	Road Use Survey	69
	Motor Vehicle Allocation Survey	71
	Sample Forms FS-1, RU-1, HPS-325, HPS-326	74
PART VI	Road Life Study	75
	Definitions	75
	Form RL-1	76
	Form RL-2	80
	Sample Forms RL-1 and RL-2	86
PART VII	Summary	87



Three Different Modes of Transportation
Highway, Railroad and Water



Road Constructed Primarily as a Scenic Route

PART I

THE NECESSITY OF HIGHWAY PLANNING

The Necessity of Highway Planning

The growth of highways in the United States is comparable in many respects to the growth of a fruit tree which a man planted originally for the pleasure of just being the possessor of a tree. The movement for the building of roads was started about twenty years ago by the incentive of having good roads on which to go for a ride somewhere outside of town for an outing, either by horse or bicycle or by that rare and rather terrifying invention, the automobile. The roads at this time were built largely for pleasure or through jealousy aroused by the fact that neighboring towns or counties had better roads. These roads seemed to be quite self-sufficient, in that they rarely had any connection with each other, and were quite indifferent, in that they never attempted to go very far nor have any specific reason for going at all. The roads, like the tree, were permitted to grow of their own volition, prompted occasionally by spurts of enthusiasm through contributions of either tax money or direct labor.

Building of roads for pleasure continued through the first decade of 1900, but there were a few men of vision who saw that if the tree were to grow in strength and bear fruit, some attention must be given to it. The trunk and the main branches must be strengthened, and so was started the movement for the establishment of the Federal Bureau of Roads and the various State Highway Departments. These leaders realized that main highways connecting cities and states must be constructed to foster the support and growth of feeder roads in the same manner that the trunk and main branches of a tree foster the support

and growth of the smaller fruit-bearing branches.

Construction of roads was financed in the beginning through property taxation, but as automobiles increased in number, taxation was placed directly upon the owner through the medium of a license and a gasoline tax. The proceeds derived from these latter sources have increased far beyond conception so that today our highways are supported in whole by the direct taxation derived through automobile ownership. This continual and increasing flow of revenue, contributed in part by the Federal Government and in part by the respective states, has made it possible to construct a national highway system which makes it feasible for us to travel throughout the nation in any direction over improved roads.

We have today approximately 330,000 miles of roads under the Federal and State Systems classed as primary roads, but many of these roads are far from satisfactory. A great number of these roads were not designed to sustain the deteriorating impact to which they are subjected due to an ever increasing flow of traffic and an ever growing movement of heavily loaded trucks and busses, nor were they designed with respect to width, alignment and grade to provide for the ever increasing speed at which the automobile of today travels. All of these factors, which fail to co-relate existing road conditions with modern traffic conditions, must be corrected and improvements projected in order to revise these obsolete conditions.

There remains another type of road which far exceeds in mileage the State and Federal roads; namely, the secondary roads throughout the nation which are estimated to aggregate some 2,700,000 miles. Heretofore, these secondary roads received no

consideration except at the hands of local authorities in their respective counties, and while a goodly portion of these roads has been improved to some extent, the major portion has received little or no attention. As each year brings nearer to completion the paving of main routes, and as there seems to be no abatement of income for road building purposes, there is a growing tendency on the part of the people to do something with the secondary roads. This movement towards improvement of secondary roads has increased in importance to the extent that the Federal Bureau of Roads now allocates a specified percentage of funds for their construction and in most states a separate department has been set up under the aegis of the Bureau to prosecute this work.

We stand today at the cross roads of highway construction, The way back cannot be retraced, we must go forward. We can arrive at our destination by going to the right and continuing improvement of the main routes or by going to the left and constructing only such secondary roads as may be demanded for selfish reasons. These two routes may offer the least resistance, but they are, by far, the longest and the costliest. The other way open to us is straight ahead by means of intelligent planning. We will encounter difficulties here because of factional jealousy, but certainly our destination will be reached with a saving of both time and money.

Our problem is not one of how many miles of roads we can build, nor of how many miles we can maintain, but one of how many miles of roads we are willing to own. The increasing demand for improvement of secondary roads, as well as revision of the present primary roads, will create an excessive strain upon

our financial resources. Unless we approach the subject of future highway construction by means of a scientific analysis of the entire highway transportation problem, we will have a structure resting upon the shifting sands of public opinion, which will require constant shoring and bracing at great expense if we are to build upward.

There is another important factor which heretofore has been given no consideration whatsoever in the field of highway construction, but which may become one of the predominating problems to contend with. This problem, which may transcend present day factors, is that of redistribution of population. Communities, in the past, were established in a somewhat concentrated pattern, brought about by the attractive forces of water and rail transportation supplemented by steam power; whereas, in the future, new communities may and probably will be established in a diffused pattern actuated by the repellent force of a more flexible motor vehicle transportation supplemented by an equally facile electrical power. We have already seen this factor taking growth in the dispersement of industry from the highly centralized plants to widely scattered branch units, in the decadence of once prosperous river and railroad towns, and in the compulsory abandonment of non-productive farming sections. We cannot ignore this possible readjustment of population entirely in planning highways of the future; because, if we do, we may invest money in roads which in years to come may have no justifiable reason for existing.



Ford Across Creek
Practically Impassable by Automobile

PART II

THE PURPOSE OF A HIGHWAY PLANNING SURVEY

The Purpose of a Highway Planning Survey

A Highway Planning Survey serves the same purpose to the road builder, and the public at large, that a diagnosis and a case history of a patient serves the attending physician. The purpose of a Highway Planning Survey can best be explained by taking each phase of the Survey, and detailing the specific purpose of that one division, and then consolidating this information into a unified statement apropos of the Survey as a unified problem.

The purpose of the Road Inventory is to secure all pertinent data pertaining to every publicly traveled road in the state. This data will be made up of such information as the location, length, width, material, condition and drainage facilities on each road; the location, type, load bearing capacity, safety of approach and condition of bridges; the location, visibility, safety condition and accident record of all railroad crossings; the location of all houses, farms, schools, churches, business establishments, industries, railroads, navigable streams, airports, and local road building material deposits, on or near each road; the terrain and the types of soil in every section traversed by each road.

Data acquired, as a result of a state-wide Traffic Survey, will make it possible to segregate all roads as to their relative traffic-carrying importance. This information will consist of density counts on key circuits, where traffic will be tabulated by the hour and classified as to passenger cars, trucks and busses, both local and foreign; the direction from which these vehicles came and in which they are going. Weight data of

trucks and busses will also be secured at designated points, whereby will be determined the type, weight, width, length, height, load capacity, load carried, commodity carried, place of ownership, origin, destination and trip mileage for every truck and bus that is stopped and weighed. Blanket counts at numerous county road intersections will supply information as to secondary road traffic. Origin and destination studies will provide a comprehensive history of individual travel for a statewide average. Automatic electric counters will supply a continuous picture of traffic flow over selected primary and secondary roads.

The Financial phase of the Survey will disclose what portion of taxes has been, and is being, expended for the construction of roads, Federal, State, and County; how much is allocated for city streets; what percentage of the tax dollar goes towards this type of public expenditure; what proportion is paid by the urban populace and by the rural populace; what part of this burden falls upon the automobile owner and the non-owner; and to what extent highway expenses are borne by commercial users of the highways, as compared to the private individuals.

The purpose of the Road Life Study is to compile data on all types of construction and under varied traffic conditions; in order that, in the future, the life expectancy of each type of road may be brought under a practical formula, in somewhat the same manner that is employed by insurance companies in formulating the life expectancy of individuals. Research work on this phase will cover the entire history of the roads on record throughout their period of existence, from the grading to the surfacing, and on through maintenance.

Final compilation of all of this information will give us the only comprehensive picture of highway history to date. It will, for the first time, tell us how many miles of roads we have; what type they are and the nature of the territory they serve; it will provide us with complete information as to the amount and kind of traffic our roads carry; it will enlighten us as to the cost of roads and the distribution of these costs, which heretofore has been a problem of crystallogancy; it will inform us concerning the life expectancy of all types of roads; it will enable us to plan our future mode of existence from a geographic standpoint; and finally, it will greatly assist us in unravelling the very vexing problem of a national transportation system, which yearly is becoming so complex that it seriously affects our entire economic structure.



Dangerous Two Lane Underpass on Federal Route

Constructed on Point of Reverse Curve

PART III

ROAD INVENTORY

Road Inventory

Field Work

General

Inventory of roads shall be performed by a party consisting of a chief of party, recorder, chainman, and a field draftsman. The equipment necessary to prosecute the field work shall consist of the following:

Automobile (Sedan or Coach equipped with odometer)

Tire Gauge

Forestry Compass

Plumb Bob

Hand Level

50' Metallic Tape

100' Steel Tape

6' Folding Rule

Drawing Board (21" x 26")

Clip Board (9" x 13 $\frac{1}{2}$ ")

Clip Board (18" x 24")

Two Binders (18" x 24")

10' Painted Rod (3/4" x 2")

Tack Hammer

Short Handled Mattock

Inventory Tags

Box Letter File

Two Red Flags

Portable Drawing Table

6" and 12" Engineer's Scale

Two 8" Triangles (30 - 60)

Two 10" Triangles (45)

6" and 8" Protractors

36" T Square

Stationery Supplies

Forms HPS - 1, 4, 5, 6, 8, and 200

Standard Field Tables (General Land Office)

Map of County to be Inventoried

Descriptive Data of U.S.C. & G.S. Triangulation Stations
of County to be Inventoried

The party shall establish headquarters at the county seat in order that county officials may be questioned regarding information which may not be available in the field. The party chief shall then interview the county commissioner, county school superintendent, county warden, postmasters and other officials who may have road information of value to the party. Before beginning work, the chief of party shall familiarize himself with the county map and lay out inventory zones. These zones shall be bounded by definitely established features, such as state routes, major county roads, rivers or railroads. All roads shall be assigned a number, but only as they are inventoried with the exception of state routes which shall carry the number assigned to it by the state.

Odometer

The odometer shall be checked for accuracy before starting work in each county, each time the tires are changed, and on other occasions when doubt may arise as to any variation of reading. This shall be done by making a test run over a chained or known distance of five miles or more. If the odometer

distance varies more than two percent from the known distance, the tire pressure shall be changed until the odometer records the distance to the desired accuracy. A permanent record of this test run shall be made on Form HPS-200 (see sample form). The tires shall be checked each morning before beginning work and the same pressure maintained throughout the inventory in that county.

Triangulation and Traverse Stations

Description of the location of all triangulation stations, first order traverse stations, and local control stations will be furnished the chief of party. These stations shall be tied into the road, on or near which they are situated, by odometer reading, distance, and bearing.

Federal and State Projects

All Federal and State Aid Project markers shall be located on their respective roads by odometer reading, indicating the number and direction of the project.

Cities and Towns

All cities, towns and villages shall be located on roads which extend to, or through their limits. Odometer readings shall be taken at all corporate limits. The city center and the geographic center shall also be located in each case; the former being that point from which mileage is generally measured by the public, such as the court house, city hall and railroad station. Cities, towns and villages shall be listed according to the following classification:

- | | | |
|-------------------|------------|----------|
| 1. Incorporated | Postoffice | Railroad |
| 2. Unincorporated | Postoffice | Railroad |

3.	Incorporated	Postoffice	No railroad
4.	Unincorporated	Postoffice	No railroad
5.	Incorporated	No postoffice	Railroad
6.	Unincorporated	No postoffice	Railroad
7.	Incorporated	No postoffice	No railroad
8.	Unincorporated	No postoffice	No railroad

A complete inventory shall be made of all roads and streets in all unincorporated towns. Cultural items along roads through incorporated towns shall not be inventoried, but items common to all towns such as curb and gutter, sidewalks, names of streets traversed, railroad station, city and geographic center, shall be recorded. Roads and streets through sub-divisions and private mill villages which are open to public use shall be inventoried as in unincorporated towns.

Reservations

Roads through public reservations shall be inventoried and the boundaries indicated by odometer reading on each road. These reservations shall be classified as follows:

National Forest

National Forest Development

Military

Indian

Other National Reservation (kind)

State Forest

State Park

Other State Reservation (kind)



Typical Important County Road
Insufficiently Maintained

Roads

The alignment of all roads shall be established by compass bearings to full degrees and the length by odometer readings to the hundredths of a mile. The point of intersection of all curves shall be located by odometer readings and the direction of curvature by tangent bearings. All roads shall be tied into each other by odometer equalities, bearings, and road numbers by the use of inventory tags (see sample tags), and these tags shall be tacked to a tree or other object at each intersection so that the information can be readily obtained as each new road is inventoried. All roads maintained at public expense over which a four wheeled vehicle can travel shall be logged, and if they are impassable for automobile travel, they shall be measured with a hundred foot steel tape. Inventory of toll roads shall include the name of the owner, the name and address of the principal officer, and a schedule of the toll rates.

All data pertaining to road inventory shall be recorded on Form HPS-6 (see sample form). The center line of this form, which represents the road, is divided into tenths of a mile in order to facilitate the recording of odometer readings. Alignment data, bridges, railroad crossings, road intersections, city, county, section, and state lines, and such items as relate directly to the road proper shall be sketched on this center line. Special data required for bridges and railroad crossings shall be recorded on separate forms as explained in a separate succeeding section.

Cultural items shall be recorded with respect to odometer reading and distance from the center line in their proper location on Form HPS-6 (see sample form), using the symbols listed

under a separate section. All power and telephone lines, railroads, and streams shall be sketched on this form whenever they come within the line of vision of the inventory party even though they do not cross the road.

Classification of roads shall be listed in classification spaces one to five by the use of symbols as explained under a separate section. Traffic conditions on each road, as observed by the inventory party, shall be noted under remarks at the bottom of the straight line form.

Culverts

Drainage structures with a clear span of from 10 feet to 19 feet, measured along the center line of the road, shall be recorded on Form HPS-6 by odometer reading and shall be described as follows:

1. Type and material
2. Length
3. Width
4. Height (stream bed to floor or road surface)
5. Condition
6. Name of stream
7. Direction of stream flow

Bridges - General

All bridges with a clear span of 20 feet or more, measured along the center line of the road, shall be recorded on Form HPS-6 (see sample form) by odometer reading at the beginning of the structure. The name of the stream and the direction of flow shall also be indicated. Complete description of the bridge shall also be recorded on Form HPS-5 (see sample form) as follows:



Covered Bridge Resting on Solid Rock
This Type of Bridge Practically Extinct

1. Odometer reading at beginning of structure
2. Name of stream, highway or railroad
3. Kind of crossing, if over or under railroad
4. Load limit (posted or calculated)
5. Construction date
6. Overall length of bridge along center line of road
7. Clear span or spans
8. Type of substructure for each span, whether piers, abutments, pile or frame bents, or columns, and the kind of material
9. Type of superstructure for each span, whether truss (name), girder (beam or stringer), integral slab and beam, slab, arch, suspension, cantilever, or covered, and the kind of material
10. Kind of material in floor
11. Highwater mark above or below bridge floor
12. Rip rap, kind and location
13. Condition of substructure, superstructure, and floor, whether good, fair, or poor, and description of serious defects
14. Condition of paint
15. Minimum lateral roadway clearance between curbs, railings, or bridge members
16. Sidewalks, side and width
17. Distance from road surface to stream bed or top of rail
18. Distance from road surface to bottom of portal
19. Clear distance of opening above stream bed
20. Remarks as to adequacy of the opening, and as to location

of the bridge with respect to alignment and grade of the approaches

Draw Bridges

The spans on draw bridges shall be described according to the following classifications:

1. Bascule - single leaf (hand or power operated)
2. Bascule - double leaf (hand or power operated)
3. Vertical lift (hand or power operated)
4. Rotary (hand or power operated)

The type of protection at all draw bridges shall also be described, using the same classification, listed on Form HPS-4 (see sample form), as is used for railroad crossings.

Toll Bridges

Additional information shall be obtained on all toll bridges as follows:

1. Name of owner
2. Name and address of principal officer
3. Schedule of toll rates

Ferries

The following information shall be secured on all ferries as they are encountered on road inventory:

1. Name of river
2. Estimated width of stream at low water
3. Capacity of boat (passenger automobiles)
4. Motive power (hand or power)
5. Number of scheduled round trips in 24 hours
6. Hours of service each day
7. Whether toll or free
8. Type of protection (see Form HPS-4 for classification)



Railroad Crossing on County Road
Visibility Completely Obstructed in Both Directions

9. Name of owner and name and address of principal officer
10. Schedule of toll rates

Railroad Crossings

All railroad crossings shall be located by odometer reading on Form HPS-6 (see sample form), but a complete description of each crossing shall be made out on Form HPS-4 (see sample form). The data to be secured shall consist of the following:

1. Odometer reading at crossing
2. Name of railroad
3. Number of nearest mile post and distance from crossing
4. Number of main line and other tracks
5. Approximate gradient of road approaches
6. Angle of crossing
7. Alignment of railroad (tangent or curve)
8. Clear view distance
9. Types of protection

Sight distances at points 300 feet from the crossing shall be noted and all sight distances over 2000 feet, as measured along the railroad, shall be considered as unlimited. The view may be greatly restricted at the 300 foot point, but may become unlimited at a point closer to the crossing. If such a condition exists, the point of greatest sight distance shall be located, and any obstructions noted on the form, giving the distance of these obstructions from the road and the railroad.

Cultural Items with Symbols

All cultural items shall be inventoried along each road, indicating by means of a small square on Form HPS-6 (see sample form) the location with respect to the road. The following

symbols shall be used in conjunction with the small square to designate the kind of item inventoried.

- AP Airport
- BL Airway Beacon Light
- CA Community Auditorium
- BP Ball Park
- Barn Without Dwelling
- B Business (without residence - kind)
- BH Business and Home Combined
- CG Cattle Guard
- CP Cattle Pass
- Cem. Cemetery
- C Church
- CG Cotton Gin
- CH Court House
- D Dairy
- H Dwelling
- FG Fair Grounds
- F-1 Farm Unit (2 or more houses). Plantation, estate or farm with central dwelling and tenant dwellings on the farm.
- F-2 Farm Unit (1st Class). Dwelling with moderate or large sized barn and outbuildings. A place whose general appearance indicates any phase of agriculture as the principal business.
- F-3 Farm Unit (2nd Class). Rural dwelling with small acreage, generally less than five acres, with few outbuildings; appearances indicating the occupant earns living elsewhere.

FS	Filling Station
FT	Fire Tower
FL	Fishing Lodge
GG	Golf Grounds
GP	Gravel Pit
I	Industry (kind)
L	Lake (name)
LRM	Local Deposit Road Material
LC	Logging Camp
M	Mine (kind)
PO	Postoffice
PP	Public Park
RS	Railroad Station
RH	Resort Hotel
SM	Saw Mill
SP	Scenic Point
S	School
TH	Tenant House
TC	Tourist Camp
TS	Turpentine Still
V	Prefix for Vacant Property
⎵⎵⎵	Power Lines
⎵⎵⎵	Transmission Lines
⎵⎵⎵	Telephone and Telegraph Lines
△	Triangulation Station (number)
BM	Bench Mark (number and elevation)
∧ ∧	Guard Rail

Road Classification

All roads shall be classified in spaces one to five on Form HPS-6 (see sample form), and the limits of each classification shall be indicated by arrows. This classification shall conform to the following types and shall be recorded by the numbers assigned to each type.

Space one shall be used to designate the type of grading, the type of surfacing, and the type of base. Sidewalks and curb and gutter shall also be designated in this space when a road continues through a city or town.

Types of Grading:

1. Primitive Road
2. Unimproved Road
3. Graded and Drained Road (Low Type)
4. Graded and Drained Road (Intermediate Type)
5. Graded and Drained Road (High Type)

Types of Surfacing:

10. Soil Surfaced Road
11. Natural Sand Clay or Top Soil
12. Sand Clay or Top Soil ($\frac{1}{3}$ " or $-\frac{3}{4}$ " thickness)
13. Quarry Waste (size less than $\frac{1}{4}$ inch)
14. Sand Clay stabilized with Calcium Chloride
15. Subgrade stabilized with Bituminous Material
19. Other Types
20. Gravel or Stone Road (coarser than sand)
21. Chert ($\frac{1}{3}$ " or $-\frac{3}{4}$ ")
22. Clay Gravel ($\frac{1}{3}$ " or $-\frac{3}{4}$ ")
23. Crushed Stone ($\frac{1}{3}$ " or $-\frac{3}{4}$ ")

- 24. Disintegrated Rock (1/3" or -3")
- 25. Pebble Soil (1/3" or -3")
- 26. Shell (1/3" or -3")
- 27. Slag (1/3" or -3")
- 29. Other Types
- 30. Bituminous Surface Treated (1" or less in thickness)
 - 31. Single Surface Treatment - Slag
 - 32. Single Surface Treatment - Stone
 - 33. Double Surface Treatment - Slag
 - 34. Double Surface Treatment - Stone
 - 35. Double Surface Treatment - Slag and Stone
 - 36. Rock Asphalt
 - 39. Other Types (kind)
- 40. Mixed Bituminous Road (over 1" in thickness)
 - 41. Road Mix in Place - Sand
 - 42. Road Mix in Place - Gravel
 - 43. Road Mix in Place - Stone
 - 44. Road Mix in Place - Slag
 - 49. Other Types (kind)
- 50. Bituminous Penetration Road (over 1" in thickness)
 - 51. Penetration - Stone
 - 52. Penetration - Gravel
 - 53. Penetration - Slag
 - 59. Other types (kind)
- 60. Bituminous Concrete or Sheet Asphalt Road (over 1" in thickness)
 - 61. Bituminous Concrete
 - 62. Limerock Asphalt

- 63. Sand Asphalt or Sand Asphalt Base
- 64. Sandrock Asphalt
- 65. Sheet Asphalt
- 69. Other types (kind)
- 70. Concrete Road
 - 71. With expansion joints at regular intervals, no center longitudinal joint
 - 72. With expansion joints at regular intervals and center longitudinal joint
 - 73. Without regularly spaced expansion joints
 - 74. Cement Bound Macadam
 - 75. Vibrolithic Concrete
 - 76. Concrete Road with Bituminous Surface not less than one inch thick
 - 79. Other types (kind)
- 80. Brick Road
 - 81. With Bituminous Filler
 - 82. With Cement Grout Filler
 - 83. With Bituminous Mat less than 1" thick
 - 84. Other types (kind)
- 90. Block Road
 - 91. Asphalt Block
 - 92. Stone Block
 - 93. Wood Block
 - 94. Block Road with Bituminous Mat less than 1" thick
 - 99. Other types (kind)

Types of Base:

- 1. Bituminous Concrete
- 2. Bituminous Macadam

3. Chert
4. Clay Gravel
5. Concrete
6. Crushed Rock
7. Limerock
8. Pebble Soil
9. Sand Clay or Top Soil
10. Shell
11. Other types (kind)

N - Sidewalks (show side and distance from center line)

O - Curb and Gutter (show side and distance from center line)

Space two shall be used to describe the general condition, the defects if any, and the drainage of the road.

Condition:

C-1 Good

C-2 Fair

C-3 Bad

Defects:

D-1 Not serious

D-2 Corrugated

D-3 Scaled

D-4 Raveled

D-5 Warped

D-6 Badly Cracked

D-7 Disintegrated

D-8 Soft Spots

D-9 Rutted



Well Maintained Secondary Road
Graded and Drained and Gravel Surfaced

Drainage:

Side Ditches

1. None
2. Incomplete
3. Complete

Cross Drains

4. None
5. Incomplete
6. Complete

Space three shall be used to designate the width order of the road, the types of soil and the topography of the section through which the road extends.

Width Order:

Surface

Roadbed (paving plus shoulders)

Right of Way

Type of Soil:

- S-1 Sand
- S-2 Sand Clay
- S-3 Pebble Soil
- S-4 Clay
- S-5 Rocky

Topography:

- T-1 Flat
- T-2 Rolling
- T-3 Hilly
- T-4 Mountainous

Space four shall be used to describe the administrative system under which the road is maintained and to designate the use of the road according to route. School bus routes shall be verified by the county school superintendent and mail routes by the postmasters.

Administrative System:

- SR State System (rural)
- SM State System (municipal)
- SF State Forest
- SP State Park
- SI State Institution
- CR County System (rural)
- FF Federal Forest
- FP Federal Park
- FM Federal Military

Routes:

- SB School Bus
- CB Common Carrier (bus)
- CT Common Carrier (truck)
- RFD Rural Free Delivery Route
- SMR Star Mail Route

Space five shall be used for any additional descriptive information of the road.

STATE HIGHWAY BOARD OF GEORGIA
DIVISION OF HIGHWAY PLANNING SURVEY
IN COOPERATION WITH U. S. BUREAU OF PUBLIC ROADS

DAILY TIME AND WORK REPORT OF ROAD INVENTORY PARTY

District <u>1</u> Date <u>Jan. 4,</u> 193 <u>8</u>		NAME _____	Hours _____
County <u>Chattooga</u>		Party Chief <u>A. H. Stephens</u>	<u>8</u>
Zone <u>South West</u>		Recorder <u>G. A. Nellis</u>	<u>8</u>
(Show Section of County)		Draftsman <u>None</u>	
ODOMETER READINGS		Chainman <u>None</u>	
	Time of Day		
Start from Hdqts. <u>37629</u>	<u>7:45 AM</u>	Hours Field Work <u>8</u>	
Begin Day's Work <u>37635</u>	<u>8:00 AM</u>	Hours Lost in Field <u>0</u>	
End Day's Work <u>37683</u>	<u>4:30 PM</u>	Hours Misc. Work <u>1</u>	
Return to Hdqts. <u>37691</u>	<u>4:45 PM</u>	Remarks: (Explain in complete detail on back of this s	
Total Miles Traveled <u>62</u>		Misc. Time; Time Lost; Slow Progress; Exce	
Travel Per Mile Inventoried <u>2.36</u>		Travel)	

RECORD OF ROADS INVENTORIED

Road Number	From	To	Miles Inventoried (Nearest tenth)	Remarks
27	35.42	40.04	4.6	
28	42.71	46.30	3.6	
29	48.07	52.37	4.3	
30	54.84	55.19	0.4	
31	56.54	60.87	4.3	
32	64.38	64.93	0.6	
33	67.47	72.75	5.3	
11	80.17	83.24	3.1	
		(See Back)		
TOTAL OR SUB-TOTAL			26.2	

Route to follow to arrive at first road to be inventoried next day and probable roads to be inventoried next. (Give numbers of principal roads; use back of form if necessary.)

Go west on Ga. #48 approximately 3 miles west of junction with Ga. #114. Will start on this road and run south.

Res. Address: City Summerville
Street 14 Main Street
Phone Number None
Office Address Same
Location Sketch at Same

I Certify that this Report is Correct.

A. H. Stephens

(Chief of Party)

Original, Atlanta Office; Duplicate, District Supervisor; Triplicate, Chief of Party.

RECORD OF ROADS INVENTORIED

REMARKS:

6 Special Bridge Sheets

210 PI's located

3 Railroad Crossing Sheets

35 Bridges between 10' and 20'

One half hour lost due to inspection visit of District Supervisor.

Roads slowly drying out, in somewhat better condition.

One hour at night devoted to making up Form HPS-8 and laying out the next day's work.

Northpoint
Here

STATE HIGHWAY BOARD OF GEORGIA
DIVISION OF HIGHWAY PLANNING SURVEY
In Cooperation With United States Bureau of Public Roads
RAILROAD GRADE CROSSING SHEET

Sheet No. 1
District No. 1
County No. 027
Party No. 2
Road No. 19
Odometer Reading 36
H.P.S. Crossing No. 368
R.R. Crossing No. 132
Date 12-31-37

Name of Railroad Central of Georgia

Number of Nearest R.R. Mile Post 200
Road Direction from Crossing 0-40 No. 200 Direction S

Number of Main Line Tracks 1

Number of Other Tracks 0

Road Approaches to R.R. Crossing

Approximate Gradient (+) or (-)

M -1 % N


N 200 Length -2 % 100 Length -1 % O

O --- Length --- % 300 Length -4 % P

P -4 % Q

Show Breaks in Grades and Length of Grades Near Crossing. ("N O" "O P")

Make sketches and note all obstruct showing distance from railroad and high Where this layout is not suitable for sketc a crossing, use back of form.



CHECK TYPE OF PROTECTION

0. No Warning Signal
☒ 1. Signs Only
2. Bells
3. Lights Stationary
4. Lights Flashing
5. Lights and Bells
6. Wigwag
7. Wigwag & Lights
8. Wigwag & Bells
9. Wigwag, Lights & Bells

	From	To	Total
Watchman Hours on Duty	Manual	Automatic	
Gates			
Barriers			
Chain or Cable			
Other Protective Devices			

NOTE

Record between arrows on ske the approximate distances along r road center line representing the cl views from points "N" and "P" respe ively. If the view along the track is 20 feet or more record same as unlimited.

Indicate points of greatest sight distance as f lows:

- (1) Approaching track in direction of survey. Between "N" and clearance of nearest m track.

Looking to right:
Greatest sight distance along railroad 20
Distance, point of observation to center of crossing (point "O") 20

Looking to left:
Greatest sight distance along railroad 20

- (2) In reverse direction beyond crossing. Between "P" and clearance of nearest m track.

Looking to right:
Greatest sight distance along railroad 20

Distance, point of observation to "O" 20

Looking to left:
Greatest sight distance along railroad 20

Distance, point of observation to "O" 20

Clearance point may be considered as 15 ft measured from driver's position in car to cent of track.

STATE HIGHWAY BOARD OF GEORGIA
DIVISION OF HIGHWAY PLANNING SURVEY
IN COOPERATION WITH U. S. BUREAU OF PUBLIC ROADS

BRIDGE SHEET—ROAD INVENTORY
(See Note 2)

Dist. No. 1
County Bartow
Road No. 61
Party No. 2
Sheet No. 1

Date Nov. 11, 1937

Odometer Reading 76.15 Name of Pettit Creek
(Highway, Stream or Railroad)

Kind of Crossing (Note 1): Underpass—Simple RR No. _____: Overpass RR No. _____
Underpass—Combined RR No. _____: (Note 6) No. Tracks _____

DESCRIPTION OF STRUCTURE

Calculated Load Limit 20 T: Posted Load Limit None: Bridge No. None

Overall Length of Bridge Along Center Line of Roadway 120'

Construction Date: Unknown

SPANS		TYPE AND KIND OF MATERIAL				
		Timber, treated or untreated; concrete, steel, stone, rubble or brick masonry, dry rubble, etc. (See Note 4)				
		SUBSTRUCTURE		SUPERSTRUCTURE		FLOOR
No.	(Note 3) Length	Type	Material	Type	Material	Material
<u>1</u>	<u>115½'</u>	<u>2</u> <u>Abutments</u>	<u>Concrete</u>	<u>Pratt</u> <u>Truss</u>	<u>Steel</u>	<u>Oak Plank</u>

For Culverts and Arches—See Note 8.

Highwater Mark _____ Ft. Above or 4 Ft. Below Bridge Floor

Rip Rap; Give kind and location: None

General Condition of Bridge: Check if Good, Fair, or Poor;

Describe defects if serious.

	Good	Fair	Poor
Superstructure	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Floor	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Substructure	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Loose Planks

Paint: Good X, Fair _____, Poor _____, Badly corroded or rusted _____

Clearances: Roadway (Note 5) 16'; Sidewalk widths: Right None, Left None; Surface of Road to Stream Bed 18'. (If overpass, show distance to top of rail); Surface of Road to bottom of Portal 14½'

(Minimum overhead clearance); Clear distance of opening above stream bed 16½' (Waterways only).

Remarks: Opening adequate. Approach to Bridge good-Visibility for 700',
Grade 0% for 550', + 3% for 150'. Approach from Bridge bad-Curve at
end of Bridge-Visibility for 200', Grade + 8% for 200'. Steel handrail
both sides.
(See Reverse Side for Notes)

BRIDGE SHEET — ROAD INVENTORY

NOTES:

1. Show kind of crossing by checking descriptive item applicable. For multiple span bridges give complete information on each span, including approach spans. If underpass or overpass, show railroad number of structure.
2. Sketch on Form HPS-6 approximate angle of structure with respect to center line of road and show direction of stream flow.
3. On arch bridges show clear span face to face abutments at spring line. On metal bridges show length of steel. Skew arch spans to be measured at right angles to face of abutments at spring line.
4. Show actual type construction under one of the following general types: Truss, Girder (Beam or Stringer), integral slab and beams, Slab, Arch, Suspension, Cantilever or Covered Bridge as shown in the Manual.
5. Give minimum lateral clearance. Where traffic lanes are separated by bridge members, show width of each lane separately.
6. Give information on the span over the highway only.
7. Under remarks give notation of "Adequacy" or "Inadequacy" of bridge opening.
8. For multiple span culverts show number of units and length of each under "Spans." Show "Type and Material" under substructure and total length of bridge in place provided. For arches fill in all items applicable.

DISTRICT 1		COUNTY Polk		115		ROAD NUMBERS 1		1		27		SURVEYED BY H. L. Holley		O. Brimberry		DATE Dec. 9, 1937		PAGE NO. 5	
NUMBER		NAME		NO.		COUNTY		STATE		U. S. ROUTE		CHIEF OF PARTY		RECORDER		SHEET 1 OF 1 SHEETS			
SCALE 4 in. = 1 mile		MILES THIS SHEET 8.52		DRAWN BY W.F.D		CHECKED BY H.R.J.		REVISED		DATE		CHECKED BY DISTRICT SUPERVISOR H. R. Jacobson							
SIGHT DISTANCE	OVER 500'																		
	500'																		
GRADE	500'																		
	500'																		
HORIZONTAL CURVATURE	OVER 500'																		
	500'																		
ALIGNMENT P.C. - P.T. - P.T. BEARINGS AND ODOMETER READINGS	OVER 500'																		
	500'																		
CLASSIFICATION SPACES	OVER 500'																		
	500'																		
SIGHT DISTANCE	OVER 500'																		
	500'																		
GRADE	500'																		
	500'																		
HORIZONTAL CURVATURE	OVER 500'																		
	500'																		
ALIGNMENT P.C. - P.T. - P.T. BEARINGS AND ODOMETER READINGS	OVER 500'																		
	500'																		
CLASSIFICATION SPACES	OVER 500'																		
	500'																		

State and Federal Route - Traffic heavy at all times.

STATE HIGHWAY BOARD OF GEORGIA

DIVISION OF HIGHWAY PLANNING SURVEY

IN COOPERATION WITH U. S. BUREAU OF PUBLIC ROADS

Dist.No. 1Party No. 1

COORDINATE SHEET

Date Dec. 9, 192

Odometer Correction

Factor 0Road No. Ga. 1, US 27 County Polk Location South from Cedartown
 Equalities: 591.91 Beg. Road No. 1 498.31 Road No. 6
600.43 End Road No. 1 600.43 Road No. Haralson Co. Line

Sta.	(1)	(2)	(3)	Latitude (4)			Departure (5)		
	Odometer	Distance	Bearing	+	-	Total	+	-	Total
0	591.91								
1	92.35	.44	S-0-0		44	- 44			
2	92.90	.55	S-14-E		53	97	13		+
3	93.37	.47	S-03-E		47	144	2		+
4	94.16	.79	S-18-W		75	219		24	-
5	94.55	.39	S-04-W		39	258		3	+
6	95.08	.53	S-17-W		51	309		16	+
7	95.47	.39	S-10-E		38	347	7		+
8	95.68	.21	S-45-E		15	362	15		+
9	96.16	.48	S-77-E		11	373	47		+
10	96.30	.14	S-55-E		8	381	11		+
11	96.62	.32	S-33-E		27	408	17		+
12	97.00	.38	S-13-E		37	445	9		+
13	97.20	.20	S-0-0		20	465			+
14	97.70	.50	S-18-W		48	513		15	+
15	98.12	.42	S-03-E		42	555	2		+
16	98.80	.68	S-30-E		59	614	34		+
17	99.21	.41	S-08-E		41	655	6		10
18	99.46	.25	S-05-W		25	680		2	10
19	99.69	.23	S-15-E		22	702	6		10
20	99.90	.21	S-42-E		16	718	14		12
21	600.43	.53	S-27-E		47	-765	24		+
22	-----								
23	Intersecting Road Equalities:								
24	592.13 Rd. #1 =	28.15 Rd. #10	95.36 Rd. #1 =	37.03 Rd. #78					
25	92.37	70.12	#100	96.46	23.10	#11			
26	92.70	73.46	#102	97.41	90.20	#10			
27	93.01	10.74	#9	98.12	25.06	#11			
28	93.69	19.53	#112	98.80	98.11	#11			
29	94.08	93.75	#69	99.41	26.36	#11			
30	94.12	74.87	#103	99.80	06.88	#11			
31	94.27	48.83	#79	600.12	08.82	#11			
32	94.72	75.56	#104						
33	-----								
34	Triangulation Stations:								
35									
36	#19A-50	44' W of CL at 94.25							
37									
38	#19A-46	22' W of CL at 99.42							
39	-----								
40									
TOTAL		8.52		---	765	-765	207	60	+

Columns 1, 2 and 3, and (+) and (-) of 4 and 5 computed by:

Columns 4 and 5 computed by:

H. L. Holley (Party Chief)

W. F. Davis (Field Draftsman)

Checked by:

Checked by:

W. F. Davis (Field Draftsman)

H. R. Jacobson (Supervisor)

STATE HIGHWAY BOARD OF GEORGIA
DIVISION OF HIGHWAY PLANNING SURVEY
In Cooperation with U. S. Bureau of Public Roads

ODOMETER CORRECTION FACTOR

O. T. Ray, State Director
Highway Planning Survey
305 Bona Allen Building
Atlanta, Georgia

Attention Assistant Director in Charge of Road Inventory

This is to certify that the odometer in the Chevrolet
(Kind of Car)

bearing Georgia license number 3598-C 1938
(State)

owned by H. L. Holley and operated by H. L. Holley

has been tested and in my opinion is in a satisfactory condition for field use
in connection with the Road Inventory.

Odometer Check

Description of Location of Test Run FAP #34-Haralson County, traveling East
on US #78, Ga. #8 from FAP marker in Bremen to FAP marker on the
Haralson-Carroll County Line.

Measured Distance.....	<u>5.648</u> Miles
Odometer Distance.....	<u>5.65</u> Miles
Odometer Error.....(✓ or -)	<u>0.00</u> Miles
Error - percent.....(✓ or -)	<u>0.00</u> Percent
Correction Factor.....	<u>0.00</u>
Rear Tire Pressure.....	<u>32</u> Lbs.

Remarks: New concrete road. Same test run made by the District
Supervisor in opposite direction with the same results.

Date January 21, 1938

Supervisor Herbert R. Jacobson

District #1 - Cartersville

Original to Atlanta Office
Duplicate to District Supervisor
Triplicate to Chief of Party

INVENTORY TAG

FRONT

W A R N I N G
PENALTY FOR
DISTURBING THIS TAG

—•—

STATE HIGHWAY BOARD OF GA.
Division Of Highway Planning
Survey in Cooperation with

U. S. BUREAU
of
PUBLIC ROADS

Road No.	10
Odometer Reading	28.15
Direction Traveling	E-0-0
Zone No.	3
Party No.	1
Date	12-10-37
Time	10:05
<hr/>	
Intersection Road No.	1-South
Odometer Reading	92.13

Begin Road No. 10

BACK

Drafting

Map Series

The data secured by road inventory parties is so complete in detail that it is possible to construct a series of maps which will give to us the first true picture of our entire transportation system throughout the nation. Analysis of this series will not only give us a basis for future highway construction, but will also provide us with the means of routing all types of traffic. The latter factor alone will be of vital importance because of the effect it will have on accident control and also because it will permit us to economize and unify our entire distribution system.

The kind of maps recommended for counties and states are as follows:

County Series:

1. Base Map
2. General Highway and Transportation Map
3. Bus and Truck Map
4. School Bus Route Map
5. Postal Route Map

State Series:

1. Base Map
2. Highway Map
3. Transportation Map

Each type of map should contain the following information:

County Series:

Base maps should show:

1. State, county and township boundaries and names

2. Congressional or U. S. survey township and section lines, where actually established by survey
3. Boundaries of all Federal, State, and local parks and reservations with name and class of each
4. Corporate limits of all cities
5. Geographic and city center of all cities and villages
6. Names of all cities and villages
7. All bays, lakes, rivers, canals and important minor drainage with names
8. All main drainage and irrigation ditches
9. All railroads and railroad stations in rural areas and within cities, with name of operating companies
10. All rural roads, plotted as open bands
11. Federal and State highways only, plotted as open bands, through incorporated cities
12. Projection of main roads beyond county lines, indicating nearest important town
13. All important highway bridges, indicating the type
14. All railroad crossings, indicating grade crossings, underpasses and overpasses
15. All cultural items inventoried in rural areas
16. The population by figures of all urban places with a population of 1000 or over
17. Names of adjoining counties and bordering states

General highway and transportation maps should show, superimposed upon the base map features, the following information:

1. Surface types, by symbol, of all roads carried on base maps

2. By symbols, navigable waters and waters actually navigated for public commercial transportation
3. All commercial and other airports by symbol and name
4. The numbers of all roads designated as U.S. highways and as State routes
5. By the letters FAS, all roads included in the approved Federal Aid Highway System
6. The slope distance in miles, and tenths of miles, between the following points:
 - (a) Between the center of incorporated places and their corporate limits
 - (b) Between corporate limits and the nearest significant highway intersections
 - (c) Between centers of small towns and villages and the nearest significant highway intersections
 - (d) Between significant highway intersections in rural territory
 - (e) Between county seats and all cities and towns of 1000 population or more via the shortest and best route

Bus and truck maps should show, superimposed upon the base map features, all U.S., State, and Federal-Aid Highways; and by symbols, all roads used by:

1. Public bus lines
2. Common carrier truck lines
3. Both public bus lines and common carrier truck lines

School bus maps should show, superimposed upon base map features, all U.S., State, and Federal-Aid Highways, and by symbols, all roads used by school buses.

Postal route maps should show, superimposed upon base map features, all U.S., State, and Federal-Aid Highways, and by symbols, all roads used by:

1. Rural Free Delivery mail routes
2. Star Mail routes

State Series:

The base map should carry the following information:

1. County lines
2. Federal and State reservations
3. Cities and towns at junctions of U.S., Federal-Aid, State, and important secondary highways, county seats and other towns on routes between main road intersections
4. All principal drainage with name
5. U.S. numbered highways, Federal-Aid, and State highway systems, and all important county or local roads, by open bands, without indication of class or surface type
6. Railroads without name of operating companies
7. Each degree of latitude and longitude represented by fine lines
8. Names of adjoining states
9. Names of adjoining counties in bordering states

The highway map should show, superimposed upon the features of the base map, the following additional features:

1. The surface type of all shown roads, by symbol within road bands
2. Numbers of all roads designated as U.S. Highways
3. Numbers of all roads designated as State Routes

4. Designation of Federal-Aid highways by use of the letters FAS
5. Slope distance, to the nearest mile, between cities and villages of 1000 population or more

The transportation map should show, superimposed upon features of the base map, additional information as follows:

1. The use of roads, by symbols within the open bands, as:
 - (a) Public bus routes
 - (b) Common carrier truck routes
 - (c) Combined public bus and common carrier truck routes
2. Names of railroad operating companies
3. Commercial air routes and public and commercial airports
4. Navigable waterways, including canals, indicating those used commercially
5. U.S., State, and Federal-Aid highways

Drafting Procedure

All roads shall be plotted by field draftsmen, upon completion of inventory in each county, to the scale of one or two inches to the mile, depending upon the size of the county. This plotting shall be done upon hard plates upon which have been drawn mercator grid lines and upon which have been located and numbered all triangulation stations within the county, adjacent to either primary or secondary roads. Since the road inventory party chief has a complete description of all triangulation stations within each county, he can definitely locate a station

near roads being inventoried with respect to each road. These stations can then be located upon the grid plate by the field draftsman by means of X and Y coordinates. The triangulation stations thus established shall be used as control points in plotting the entire road system of a county.

All plotting of roads shall conform to a maximum error of closure of 5%; based upon the ratio of overrun or underrun distance of closure with the tie-in point to the total road mileage. This error of closure is generally too great since an experienced and careful party chief should be able to tie in road intersections within the limits of 1% or 2% error.

The draftsman shall begin plotting in each county by selecting such roads as are tied into triangulation stations, and making adjustments between these stations in order to establish the correct location of the road situated between triangulation stations. Once these roads have been adjusted, every point on them will become a control point. When the control roads have been definitely established, the other roads shall be plotted in their true position by making the necessary adjustments with respect to the various control roads.

Plotting is done by the latitude and departure method directly from the data compiled on Form HPS-8 (see sample form). The total columns on these forms for the latitude and departure of each point shall not be filled in until the extremities of the road have been plotted to ascertain whether or not an adjustment is necessary to correct for error of closure. If the error of closure is found to be very small, the adjustment shall be made by adding or subtracting one hundredth to or from each of

the longest courses in either latitude or departure as the case may be. If the error of closure is greater, a mathematical adjustment shall be made as exemplified on the sample Form HPS-8 following this section. Data on this form indicates that the compass needle has been deflected to the north and west, probably by some local attraction, which requires that the latitudes and departures be adjusted in order that bearings may be corrected to their true position.

All roads must be so plotted that they tie in at the county line with the same road which has been inventoried in the adjoining county. The controlling factor in this case will be the scale distances of the end point on the road from the nearest mercator grid lines.

After the entire road system of a county has been plotted and checked, all road structures and cultural items on each road shall be plotted upon the grid plates from the information noted on Form HPS-6, using the designated standard symbol for each item (see standard symbol plate). After all information has been included on these grid plates, tracings shall be made for the various types of maps previously described under the county and state series. Samples of these maps are shown at the end of this section.

STATE HIGHWAY BOARD OF GEORGIA

DIVISION OF HIGHWAY PLANNING SURVEY

IN COOPERATION WITH U. S. BUREAU OF PUBLIC ROADS

Dist. No. 2Party No. 1

COORDINATE SHEET

Date Oct. 27, 19

Odometer Correction

Factor 0Road No. 34 County Rockdale Location South of ConyersEqualities: 84.00 Beg. Road No. 34 14.63 Road No. 5688.47 End Road No. 34 29.16 Road No. 86

Sta.	(1)	(2)	(3)	Latitude (4)			Departure (5)		
	Odometer	Distance	Bearing	+	-	Total	+	-	Total
0	84.00								
1	84.35	.35	N-05-E	35		34	3		
2	84.60	.25	N-02-E	25		58	1		
3	84.95	.35	N-25-W	32		89		15	- 1
4	85.20	.25	N-10-W	25		113		4	- 1
5	85.38	.18	N-45-E	13		125	13		
6	85.68	.30	N-02-E	30		154	1		
7	86.05	.37	N-40-W	28		181		24	- 2
8	86.50	.45	N-70-W	15		195		42	- 5
9	86.72	.22	S-70-W		8	187		21	- 7
10	87.02	.30	S-65-W		13	173		27	- 10
11	87.37	.35	S-68-W		13	160		32	- 13
12	87.52	.15	S-30-W		13	146		8	- 13
13	87.75	.23	S-10-W		23	122		4	- 14
14	88.05	.30	S-05-E		30	91	3		- 14
15	88.25	.20	S-01-W		20	70		0	- 14
16	88.47	.22	S-10-W		22	47		4	- 14
17	-----								
18	Triangulation Stations:								
19	#B2-118 at 84.00			#B2-116 at 88.47					
20	-----								
21	Method of Correction:								
22	Step 1-:			Step 4-:					
23	4.47 x .05 = .22			2.03 / 1.42 = 3.45					
24	Step 2-:			14/345 x Individual Lat. =					
25	2.03 - 1.42 = .61			Individual Correction					
26	1.81 - .21 = -1.60			/ Lat. corrected -					
27	Step 3-:			- Lat. corrected /					
28									
29	Plotted Position			.21 / 1.81 = 2.02					
30	#B2-116			16/202 x Individual Dep. =					
31	A x = -160			Individual Correction					
32	B x = -144			/ Dep. corrected /					
33	#B2-116			- Dep. corrected -					
34	Actual Position								
35				Step 5-:					
36				(/.61) - (-.14) = /.47					
37	#B2-118			(-1.60) - (/.16) = -1.44					
38									
39									
40									
TOTAL				203	142	/ 47	21	181	- 14

Columns 1, 2 and 3, and (+) and (-) of 4 and 5 computed by:

Columns 4 and 5 computed by:

Checked by: _____ (Party Chief)

Checked by: _____ (Field Draftsman)

(Field Draftsman)_____
(Supervisor)


LEGEND FOR COUNTY BASE MAP SERIES

ROADS




PRIMITIVE ROAD
OTHER ROADS

ROAD SYSTEM DESIGNATION




UNITED STATES HIGHWAY
STATE HIGHWAY SYSTEM


RAILWAYS



RAILROAD ANY NUMBER OF TRACKS USED BY SINGLE OPERATING COMPANY




RAILROAD (ANY NUMBER OF TRACKS) USED BY MORE THAN ONE OPERATING COMPANY ON SAME OR ADJACENT RIGHTS OF WAY NOT TRACKAGE RIGHTS




NARROW GAGE RAILROAD




ELECTRIC INTERURBAN OR SUBURBAN RAILROAD




RAILROAD-STANDARD GAGE PRIVATELY OWNED



RAILROAD-NARROW GAGE PRIVATELY OWNED




RAILROAD-SERVICE ABANDONED TRACK RETAINED




RAILROAD ON STREETS OR ROADS




ELECTRIC RAILROAD ON STREETS OR ROADS




GRADE CROSSING



RAILROAD ABOVE-UNDERPASS



RAILROAD BELOW-OVERPASS



RAILROAD STATION



RAILROAD TUNNEL




RAILROAD BRIDGE


DRAINAGE




NARROW STREAM OR CREEK
WIDE STREAM OR RIVER



DRAINAGE DITCH




IRRIGATION DITCH




CANAL


BRIDGES



HIGHWAY BRIDGE
NARROW STREAM



HIGHWAY BRIDGE
WIDE STREAM




DRAWBRIDGE



SUSPENSION



ARCH




TRUSS (W. WOOD
S. STEEL G. GIRDER)


STRUCTURES




DAM




DAM WITH ROAD




DAM WITH LOCK



LEVEE



LEVEE WITH ROAD



FORD

NATURAL FEATURES



PROMINENT ELEVATION
(NUMERALS INDICATE
FEET ABOVE SEA LEVEL)



PASS



SCENIC POINT




WATERFALL

WATERWAYS




OPERATED SHIP OR BARGE
LINES ON NATURAL
STREAMS




WHARF DOCK PIER OR
LANDING




NAVIGABLE STREAMS
(IN FACT)




HEAD OF NAV.
(SMALL STREAM)



HEAD OF NAV.
(DEEP WATER)



FERRY (T.F. TOLL FERRY
F.F. FREE FERRY)



"PORT OF ENTRY"
INTERNATIONAL PORT OF
ENTRY

(CONTINUED)

PARKS AND OTHER RESERVATIONS

NATIONAL PARK : STATE PARK
NATIONAL FOREST
STATE FOREST
NATIONAL MONUMENT
MILITARY RESERVATION



MONUMENTS - SMALL



MUNICIPAL PARKS



BIRD SANCTUARIES



GAME FARMS



GAME PRESERVES



FISH HATCHERY



FORT



CAMP GROUNDS



TOURIST CAMP



CEMETERY

RECREATION AREAS



INTENSIVE RECREATION AREAS



GOLF GROUNDS



FAIR GROUNDS
RACE COURSES ETC.



PICNIC GROUNDS



PLAY GROUNDS : BALL PARKS



BATHING BEACHES



FISHING AREAS

CITY AND VILLAGE CENTERS



STATE CAPITAL



COUNTY SEAT



INCORPORATED CITY OR
VILLAGE (FIGURES INDICATE
1930 POPULATION)

1450



OTHER CITIES AND VILLAGES

BOUNDARIES



STATE



COUNTY



MILITIA DISTRICTS



CORPORATE LINES

IN USE

VACANT

DWELLINGS



FARM UNIT



DWELLING OTHER THAN FARM



ROWS OR GROUPS OF
DWELLINGS CLOSELY SPACED



SEASONAL DWELLINGS



FRESH AIR FARMS OR
REST HOMES

COMMERCIAL ESTABLISHMENTS



STORE OR SMALL
BUSINESS ESTABLISHMENT



HOTEL



FACTORY OR
INDUSTRIAL PLANT



POWER PLANT



SEASONAL INDUSTRY



SAWMILL - STATIONARY



FRUIT PACKING PLANT



TURPENTINE STILL



MINE



GRAVEL PIT



QUARRY



TANKS



WSB

RADIO STATION



GAS STATION



SCHOOLHOUSE OR OTHER
EDUCATIONAL INSTITUTION*



CHURCH OR OTHER
RELIGIOUS INSTITUTION*



COMMUNITY AUDITORIUM



HOSPITAL



CORRECTIONAL INSTITUTION*



POST OFFICE*



STATE POLICE SUBSTATION



C.C.C. CAMP



PUMP HOUSE

*FOR IMPORTANT INSTITUTION
GIVE NAME

(CONTINUED)

AIRWAYS



ARMY NAVY OR
MARINE CORPS FIELD



DEPARTMENT OF COMMERCE
INTERMEDIATE FIELD



COMMERCIAL OR
MUNICIPAL FIELD



AIRPORT HOUSING FACILITIES
DENOTED BY LETTER H
INSIDE SYMBOL



MARKED AUXILIARY FIELD



AIRPLANE LANDING FIELD
MARKED OR EMERGENCY

MISCELLANEOUS



LIGHTHOUSE



LANDMARK LIGHT BEACON



LIGHT - NAUTICAL



FOREST RANGER STATION




FOREST SERVICE
LOOKOUT STATION



TRIANGULATION STATION



TRAVERSE STATION



CATTLE GUARD



PECAN GROVE

BUS AND TRUCK SERIES

SERVICE ON
HIGHWAYS

30

*BUS AND TRUCK LINES

14

*BUS LINES ONLY

01

*TRUCK LINES ONLY

SCHOOL BUS ROUTE SERIES

SERVICE ON
HIGHWAYS

30

*SCHOOL BUS LINES

— — — — —

SCHOOL DISTRICT
BOUNDARY

POSTAL ROUTE SERIES

SERVICE ON
HIGHWAYS

30

*STAR MAIL AND RURAL
DELIVERY MAIL ROUTE

01

*STAR MAIL ROUTE ONLY

14

*RURAL DELIVERY
MAIL ROUTE ONLY

GENERAL HIGHWAY AND TRANSPORTATION SERIES

ROADS

ROAD SYSTEM
DESIGNATION

GRADED AND DRAINED ROAD

SOIL SURFACED ROAD

METAL SURFACED ROAD

BITUMINOUS
SURFACED ROAD

PAVED ROAD

FA

FEDERAL AID
HIGHWAY SYSTEM

FAS

FEDERAL AID SECONDARY
HIGHWAY SYSTEM

AIRWAYS

AIRWAY

AIR ROUTES


* NO. ABOVE BAND INDICATES
STIPPLING TYPE TO BE APPLIED

STATE-WIDE HIGHWAY PLANNING SURVEY

SECTIONAL MAP OF PEMISCOT COUNTY, MISSOURI

ILLUSTRATING STANDARD SYMBOLS AND LETTERING FOR USE ON BASE MAP

Scale 1" = 1 mile



(Features shown are for illustration only)


Plate 5 of 12 Plates

U.S. BUREAU OF PUBLIC ROADS - DIVISION OF HIGHWAY TRANSPORT

STATE-WIDE HIGHWAY PLANNING SURVEY

SECTIONAL MAP OF PEMISCOT COUNTY, MISSOURI ILLUSTRATING STANDARD SYMBOLS AND LETTERING FOR USE ON GENERAL HIGHWAY AND TRANSPORTATION MAP

Scale 1" = 1 mile



(Features shown are for illustration only)

Plate 5a of 12 Plates


U.S. BUREAU OF PUBLIC ROADS - DIVISION OF HIGHWAY TRANSPORT

STATE - WIDE HIGHWAY PLANNING SURVEY

SECTIONAL MAP OF PEMISCOT COUNTY, MISSOURI

ILLUSTRATING STANDARD SYMBOLS AND LETTERING FOR USE ON BUS AND TRUCK MAP

Scale 1" = 1 mile



(Features shown are for illustration only)

Plate 5b of 12 Plates


STATE - WIDE HIGHWAY PLANNING SURVEY

SECTIONAL MAP OF PEMISCOT COUNTY, MISSOURI

ILLUSTRATING STANDARD SYMBOLS AND LETTERING

FOR USE ON SCHOOL BUS MAP

Scale 1" = 1 mile



(Features shown are for illustration only)

Plate 5c of 12 Plates


STATE-WIDE HIGHWAY PLANNING SURVEY

SECTIONAL MAP OF PEMISCOT COUNTY, MISSOURI

ILLUSTRATING STANDARD SYMBOLS AND LETTERING

FOR USE ON
POSTAL ROUTE MAP

Scale 1" = 1 mile



(Features shown are for illustration only)

Plate 5d of 12 Plates

STATE-WIDE HIGHWAY PLANNING SURVEY

SECTIONAL MAP OF NORTH DAKOTA

ILLUSTRATING STANDARD SYMBOLS AND LETTERING FOR USE ON STATE BASE MAP

Scale 1" = 8 miles

5 0 5 10 15 20 Miles




(Features shown are for illustration only)

PLATE 8 OF 12 PLATES

STATE - WIDE
HIGHWAY PLANNING SURVEY
SECTIONAL MAP OF NORTH DAKOTA
ILLUSTRATING STANDARD SYMBOLS AND LETTERING
FOR USE ON
STATE HIGHWAY MAP
Scale 1" = 8 miles

5 0 5 10 15 20 Miles




(Features shown are for illustration only)

STATE-WIDE HIGHWAY PLANNING SURVEY

SECTIONAL MAP OF NORTH DAKOTA ILLUSTRATING STANDARD SYMBOLS AND LETTERING FOR USE ON STATE TRANSPORTATION MAP

Scale 1" = 8 miles

0 5 10 15 20 Miles



(Features shown are for illustration only)

PLATE 6-50F OF 12 PLATES

Sight Distance Survey

General

A study should be made in each state to obtain a complete record of all sight distances of one thousand feet and less. This study should embrace the location, length, and cause of all critical sight distances.

The party shall consist of four men travelling in two cars. The chief of party and the location recorder shall travel in the lead car, and the sight distance observer and his recorder shall travel in the rear car.

The equipment of the party shall consist of the following:

1. Closed automobile, equipped with specially mounted stadia rod, to be used as the lead car (see drawing)
2. Closed automobile, equipped with an overrunning clutch odometer graduated to hundreths of a mile and a specially mounted stadia interceptor, to be used as the rear car (see drawing)
3. Low-powered, short-wave radio set for inter-auto communications
4. County maps showing all road numbers
5. Inventory forms (see sample forms)
6. Stationery supplies
7. Three red flags for operating protection

Test runs over known or measured distances shall be made with both automobiles, as previously explained under Road Inventory. This must be done in order to establish and maintain a constant for each odometer.

Survey Proceedure

Both cars shall assemble at the starting point and make preparations to begin the survey. The hundreths odometer shall be set at zero and the reading of the standard automobile odometer shall be recorded.




Car number one shall proceed in the direction of the survey, following the right lane of traffic. Car number two shall wait until its interceptor, using the top of car number one as zero on the stadia rod, nearly covers the stadia rod, thereby indicating an interval of about 1000 feet. Inter-auto visibility of over 1000 feet will require no record being made, but the moment this visibility is lost, sight distance measurements will be maintained by the party chief in car number one by means of the rear vision mirror. A maximum speed of 45 miles per hour may be maintained where no sight distance measurements are necessary, but 15 miles per hour shall be the maximum when it becomes necessary to measure sight distances.

Since car number one is in the lead, and can observe a curve, grade, or any other obstruction of sight distance, the operator shall slow down to 15 miles per hour, and communications by means of the short-wave radio set will determine whether forward or backward displacements of the cars are necessary to locate the point of critical sight distance. A constant stadia check by the observer in car number two will show the approximate sight distance at any point. The relation of these various checks will determine the approximate position for minimum measurements.


An odometer sight distance measurement shall then be taken

to check the stadia rod reading. Car number one shall be notified to remain stationary. The sight distance recorder shall, at the instant of inter-auto visibility, note the stadia reading and record the odometer reading to tenths, hundreths and half-hundreths. Car number two shall then proceed to car number one and upon reaching it, the recorder shall note the full odometer reading, recording this reading above the first one (see sample notes). The difference between the two odometer readings shall then be compared with the stadia reading, allowing for a permissible error of three per cent.

All normal physical road features shall be considered in the survey. Crops affecting sight distances on curves shall be located as they are encountered. Obstructions at all important road junctions which influence traffic and at railroad crossings shall be recorded in the field notes (see sample notes). The standard automobile odometer shall be read at all important road intersections, at city and county lines, as well as at the beginning and end of the route being surveyed.




DETAIL OF STADIA INTERCEPTOR AND SUPPORTS
 SCALE - $\frac{1}{2}'' = 1'-0''$




DETAILS OF STADIA ROD
 SCALE $1'' = 1'-0''$

FRONT OF CAR STRIPED BLACK AND YELLOW ABOVE WINDSHIELD



PERSPECTIVE SHOWING FRONT OF CAR NO. 2
 NO SCALE



POSITION OF STADIA ROD MOUNTED ON RUNNING BOARD CAR NO. 1
 SCALE $\frac{1}{2}'' = 1'-0''$

METHOD FOR MEASURING
 SIGHT DISTANCE
 BY AUTOMOBILE

January 14, 1938
8:00 A.M.

Page-1

SAMPLE OF SIGHT
DISTANCE NOTES

Car-Party Chief-A.H.Stephens

1 Recorder -G.H.Nellis

Car-Observer -H.L.Holley

2 Recorder -W.F.Davis

9.05 Bushes & Trees-Right

8.165

C. of Ga. R.R.

8.100 Vertical Curve

.065

SR - #3

7.275 Horizontal Curve-Right

7.200 Railing on Concrete

.075 Bridge

4.170 Vertical-Horizontal

4.045 Curve-Right

.125 End Trees

Low

Clear Bank

CR - #42

93.6 CR - #42

Filling Corn

Station Field

3.400 Horizontal Curve-Right

3.260 Crops-Corn

.140

SR - #3

3.195 Horizontal Curve-Right

3.100 Trees, Barn & House

.095

2.215 Horizontal Curve-Left

2.050 Bushes, Trees & Garage

.165

0.465

0.325 Vertical Curve

.140

N. Corp. Line - Calhoun

4390.2

Gordon County

0.00

Begin



New Concrete Highway
Unlimited Sight Distance

Horizontal Curvature Survey

General

A record of curvature data on roads is essential to safety in view of modern speed and traffic conditions. This data should include the location, length and direction of all curves.

The curvature party shall consist of a chief of party and a recorder. The equipment for this party shall consist of the following:

1. Closed automobile equipped with an overrunning clutch odometer graduated to the hundredths of a mile
2. Curvature protractor mounted on the steering post (see drawing)
3. County maps showing all road numbers
4. Inventory forms (see sample form)
5. Stationery supplies
6. Two red flags for operating protection

Test runs over known or measured distances shall be made, as previously explained under Road Inventory, in order to establish and maintain the odometer constant.

Curvature Protractor

The protractor must be graduated to full degrees, and since each standard make of automobile has its own individual turning radius, these graduations must be determined empirically.

The automobile must be driven slowly along a known tangent which is fairly level such as a street car track and stopped carefully. A blank white cardboard, cut similar to the protractor shown in the drawing on a following page, is then placed under the steering wheel and as close to it as possible without

3

interfering with manipulation of the steering wheel. An arc is then described on the cardboard, along the outer rim of the wheel. A zero pencil line is then drawn at the midpoint of the cardboard paralleling the projection of the tangent line being followed. A narrow strip of adhesive tape is then placed around the wheel directly in line with the zero pencil line so that the latter can be projected and marked upon the tape. The steering wheel is then carefully turned in both directions until the lost motion has been taken up. The point of lost motion is marked upon the arc opposite the zero line on the adhesive tape on both sides of the center line. The steering wheel is then brought back to its original position and strips of adhesive tape are placed on the wheel opposite the lost motion marks and a line marked on these strips. A quarter-turn point is marked on the steering wheel in a similar manner by placing the right angle vertex of a forty five degree triangle at the center of the wheel and one side along the line of lost motion.

The car is then driven into a fairly level area and a number of circles described by holding the quarter-turn point of the wheel on the zero line of the cardboard. This must be done in both directions since the lost motion may be greater in one direction than in the other. As each circle is completed, the diameter is measured, in order that the average diameter for the full number of circles described may be determined.



The average diameter for a quarter-turn having measured 342 feet in diameter indicates a curvature of 34° degrees for the corresponding radius of 171 feet. The value of one degree of arc would, therefore, be one thirty-fourth of one quarter of

the steering wheel circumference. Since the diameter of the steering wheel can be determined, it now becomes a simple matter of constructing the protractor using the lost motion point as the zero degree mark in each direction.

The protractor should be designed on black paper using white lines and should be glued to a piece of masonite board cut to proper shape. It is then mounted on the steering post directly under the wheel and cross braced to the under side of the instrument board. All strips of tape are removed from the wheel except the original zero line strip, which serves as an indicator for the protractor. It will be necessary to cut a hole in the protractor board, as shown on the drawing, to permit reading of the odometer.

Survey Procedure

The party shall proceed to the starting point and make the necessary preparations to begin surveying. The car shall be driven so that the left front wheel is trained in a path parallel to the center line of the road and as close to it as traffic will permit. As a curve is approached, the P.C. shall be recorded by odometer reading and the degree of curve shall be read at the degree mark shown by the indicator. The speed of the car shall be 15 miles per hour, when measuring, in order that the operator can maintain his position with respect to the center line of the road. The degree of curvature shall be checked in going around the curve and at the end of the curve the odometer reading of the P.T. shall be recorded. The direction of the curve shall also be noted. All other data such as major road intersections, railroad crossings, city and county lines, shall also be recorded as shown on the sample inventory form.



DETAIL OF PROTRACTOR
SCALE $1\frac{1}{2}$ "=1'-0"

METHOD FOR MEASURING
HORIZONTAL CURVATURE
BY AUTOMOBILE

January 25, 1938
8:00 A.M.

Page-1

SAMPLE OF CURVATURE
NOTES

Party Chief-A.H.Stephens

Recorder -G.H.Nellis

8.35 Enter Bartow County
Leave Gordon County

S Curve

SR - #3

7.440

7.340 D - 12 Right

.100

7.340

7.280 D - 18 Left

.060

7.280

7.200 D - 16 Right

.080

CR - #101

86.8 CR - #101

Reverse

6.000

5.820 D - 12 Left

.180

5.820

5.770 D - 11 Right

.050

4.230

4.115 D - 21 Left

.115

SR - #3

2.210

2.100 D - 10 Right

.110

1.875

1.775 D - 8 Left

.100

S. Corp. Line - Calhoun
Gordon County

5680.0
0.00

Begin



Bituminous Surfaced Highway

No Traffic Hazards

PART IV

TRAFFIC SURVEY

Traffic Survey

General

A traffic survey is necessary to make possible a program of improvement whose financial requirements may be estimated with reasonable accuracy; and to develop a definite schedule of improvements in order that first consideration may be given to the heaviest demands of traffic. Compilation of all this data will enable us to visualize the total flow of traffic, peak traffic, seasonal traffic, foreign traffic and commercial traffic.

It is quite impossible to make a traffic count or to secure weight movement data on every road during each hour of every day; therefore, it becomes necessary to so conduct the survey that sample counts on definite schedules will provide us with sufficient information upon which statistical computations may be based. Since a final analysis of the completed survey depends upon the accuracy of averages, it is important that the location, count, timing, regularity, uniformity, and continuity of the record be maintained.

The entire traffic survey should be scheduled to operate over a period of a full year under two main divisions; one for the purpose of securing traffic density data for all types of vehicles, and the other for securing weight data for trucks and buses. Traffic density data shall be obtained by making counts at the following:

1. Key stations to be operated on primary roads only for compiling traffic density records on main routes
2. Blanket count stations to be operated on secondary or local roads to determine their traffic utilization

3. Origin-destination studies to determine the extent of urban and rural traffic movement
4. Automatic counters to provide a continuous record of traffic flow past selected points on primary and secondary roads

Key Stations

Key stations shall be operated in circuits of eighteen stations, the number of circuits depending upon the importance and extent of the primary roads. Georgia has twelve such circuits, making a total of 216 key stations, and in addition to this number there are 54 loadometer stations, as explained under a separate section, which are operated as a key station in conjunction with the loadometer party, thereby making a total of 270 key stations throughout the state.

One day recorder shall be assigned to each circuit operating on alternate eight-hour shifts from 6:00 A.M. to 2:00 P.M., and from 2:00 P.M. to 10:00 P.M. Fourteen eight-hour day counts shall be made at each of the eighteen stations so scheduled that a record will be obtained twice on each day of the week at separate times during the year. One night key recorder, operating from 10:00 P.M. to 6:00 A.M., shall be assigned to cover two key circuits and one loadometer circuit in order that five eight-hour night counts may be obtained on each of the key circuits, and four eight-hour night counts may be obtained on each of the the loadometer circuits.

Key stations shall be located prior to the beginning of operations and sketches prepared for the recorders (see sample sketch). Careful selection of the most important intersections

on primary roads is essential since once a station has been placed in operation, it should be operated on schedule throughout the year. Any disruption of the schedule will necessarily interfere with statistical computations.

Each recorder shall be equipped as follows:

1. Clip board (18" x 24") to hold Form HPST-15
2. Hand counters (2 or 4) depending upon the volume of traffic
3. Flashlight
4. Gasoline lantern
5. Complete set of sketches for the entire circuit (see sample sketch)
6. Master schedule of operations
7. Forms HPST-11 and HPST-15 (see sample sketches)
8. Stationery and pencils

The recorder shall travel to and from stations by automobile and shall so situate himself at a station that an unobstructed view may be had of all traffic passing through the station. The operating routine of each circuit, as determined by a pre-arranged schedule, must be adhered to. Stations shall be operated regardless of weather conditions. The recorder shall always be present at his station before the scheduled time in order that the traffic count may be started exactly on the hour and he shall remain on duty without any interruptions until the end of the eight-hour shift. Any excusable delay in reaching the post of duty, such as a flat tire, must be explained by the recorder on the back of Form HPST-15 and the actual time of beginning the traffic count must be shown. If, for example, the

shift is to begin at 6:00 A.M. and the recorder fails to reach the station on time and does not begin counting traffic until 6:20 A.M., then the first hourly count shall be shown to extend from 6:20 A. M. to 7:00 A.M. and hourly thereafter.

Form HPST-15 (see sample form) shall be used to record all information and is self-explanatory. No vehicles shall be stopped by the recorder, tabulation being made by observation alone. Every vehicle, according to its classification, shall be recorded twice; first, for the leg of the intersection on which it travels to the station, and second, for the leg on which it travels from the station. All vehicles shall be classified as local if licensed in the state under survey, regardless of how many other tags may be displayed; and all other vehicles shall be classified as foreign. Traffic count shall be recorded directly upon Form HPST-15 either by means of tally marks as each vehicle passes the station or by recording the hourly hand counter total at the end of each hour.

All descriptive information relating to each leg must conform to that shown on the station sketch (see sample sketch). Any change in weather conditions must be noted since traffic movement may be greatly affected by inclement weather. Abnormal traffic movements, created by such causes as detours, fairs or sporting events, shall be described under remarks at the bottom of the form.

Hourly totals shall be recorded at the end of each hour, if feasible, and grand totals shall be recorded at the end of the period of duty. The total of every type of vehicle coming to the station each hour should coincide with the total going from

the station for the same hour; therefore, the grand total of all vehicles for the entire eight-hour count must always be an even number.

Forms HPST-11 and HPST-15 (see sample forms) shall be mailed as soon after completion of the traffic count at each station as possible in order that checking and tabulation progress may be carried forward with the least amount of interruptions.

Computation of Twenty-four Hour Annual Average

An average twenty-four hour traffic count for the various types of vehicles is developed on an annual basis for each key station. The traffic movement on each leg of an intersection is developed separately in order that a record may be obtained for each road under investigation. In order to arrive at an annual average it becomes necessary to compute the average for each eight-hour period count on a seven-day basis and then convert these period averages into a twenty-four hour annual average.

Traffic movement on Saturdays and Sundays differs materially from that on the other five week days, so the five week day average must be combined with a Saturday average and a Sunday average, in order that a true weekly average may be computed. If, for example, a density count has been secured on four week days, one Saturday and three Sundays; the total count for the four week days shall be divided by four, then multiplied by five, the total count for the three Sundays shall be divided by three and the weekly average obtained by adding the average week day count to the Saturday count and the average Sunday count. The average computed for each of the three eight-hour periods in this manner is then added and divided by seven to obtain the

full twenty-four hour annual average.

Abnormal movements of traffic caused by unusual attractions such as fairs and sporting events, must be converted into normal movement on a yearly basis before the annual average can be computed. The following example has been assumed to clarify this conversion:

HOURS 6:00 A.M. - 2:00 P.M.

DATE	DAY	REMARKS	PASSENGER CARS
10-20-37	Wednesday	County Fair	1793
12-11-37	Saturday		616
2- 1-38	Tuesday		513
3-25-38	Friday		298
5-16-38	Sunday		444
7- 7-38	Thursday		367
8-29-38	Monday		452
Computed total vehicles (without correction)			4483
Computed total vehicles (corrected)			3124

Method of Correction:

Total week days (excluding 10-20-37) = 1630

Average week day (excluding 10-20-37) = $1630/4 = 407.5$

Excess count of 10-20-37 over average

count = $1793 - 407.5 = 1385.5$

Distribution of excess over each week

day of year = $1385.5/261 = 5.3$

Corrected average week day count = $407.5 + 5.3 = 412.8$

Computed total vehicles = $412.8 \times 5 + 616 + 444$

= 3124

Twenty-four hour annual averages computed in this manner for every leg of each key station, make it possible to prepare a traffic flow map for every city or town of importance, from the standpoint of traffic movement. Since counts made at key stations are tabulated as to types of vehicles, both local and foreign, a traffic flow map can readily be prepared for any specific type desired.

Cartersville, Georgia, being situated at the intersection of a number of important State and Federal routes, will serve as a good example for a traffic flow map. The computed twenty-four hour annual average for each key station affected by traffic to and from this city is tabulated on the following page. It was necessary to base the computation of this annual average on a four-month period since the traffic survey has not been completed, and records are only available for this four-month period. The traffic map which follows the tabulation sheet was prepared from this computed twenty-four hour annual average and is accurate only with respect to the period for which records were available.

Computed Twenty-four Hour Annual Average Count for Highways Serving Cartersville, Georgia.

Local		Foreign		Total
Passenger Cars	Trucks & Busses	Passenger Cars	Trucks & Busses	

Station 14

Leg 1 U.S. 41; Ga. 3 - To Kennesaw	1528	485	866	52	2931
Leg 2 U.S. 41; Ga. 3 - To Marietta	1520	481	723	49	2773
Leg 3 County Road - To Lost Mountain	11	5	0	0	16

Station 255


Leg 1 U.S. 41; Ga. 3 - To Calhoun	750	371	755	80	1956
Leg 2 U.S. 41; Ga. 3 - To Cartersville	1206	508	864	89	2667
Leg 3 U.S. 411; Ga. 20 - To Rome	595	180	129	9	913

Station 256

Leg 1 U.S. 411; Ga. 20 - To Canton	53	28	2	0	83
Leg 2 U.S. 411; Ga. 20 & 61 - To Cartersville	237	106	28	8	379
Leg 3 County Road - To Adairsville	6	1	0	0	7
Leg 4 Ga. 61 - To Fairmount	238	92	29	8	367

Station 286

Leg 1 Ga. 61 - To Cartersville	149	50	5	0	204
Leg 2 Ga. 61 - To Dallas	42	22	0	0	64
Leg 3 Ga. 113 - To Rockmart	118	33	4	0	155



Blanket Count Stations

Blanket count stations are, with a few exceptions, located primarily on local roads, generally at road intersections. These stations, located at points which reveal material changes in traffic density, will supply sufficient information to create a traffic profile in somewhat the same manner that a ground profile is created.

Somewhat the same procedure is followed in securing data at the blanket count stations as is done at the key stations. One recorder is assigned to a series of stations, but operates each station only one time from 8:00 A.M. to 4:00 P.M., with the exception of a few control stations, where repeated counts are essential as a basis for traffic movement interpolation for certain selected areas. These control stations shall be operated at four different times during the year in order to determine the effect of seasonal change upon traffic movement.

Stations located on primary roads shall be operated in exactly the same manner as key stations, classifying vehicles by observation and recording all data on Form HPST-15. At local road stations, however, all vehicles shall be stopped and the drivers questioned in order to properly record the data required on Form HPST-17 (see sample form). The manufacturer's rated capacity of all trucks shall also be ascertained, either from the caution plate or by interrogating the driver. Information shall also be secured from the truck drivers as to whether they are going to or coming from a railroad station, wharf or boat. This information shall be tallied at the bottom of Form HPST-15 in its respective space, in addition to recording each truck in the usual method.

Blanket count operations in a county cannot be inaugurated until road inventory has been completed, since it is necessary to have a map of the entire road system of a county, and the road inventory party chief's statement as to observed traffic conditions on each road. By the use of this map and traffic information, it will be possible to select points of apparent traffic density change such as road intersections, entrances to manufacturing plants, resorts or other important traffic objectives.

The number of blanket count stations for the entire state is necessarily indeterminate until road inventory has been completed; however, counts can be made in one county independently of another. Selected blanket count stations which are to be used as control points or nuclei for the establishment of all other blanket count stations should be so located as to be near, but off of main roads inasmuch as all main roads are sufficiently controlled by key stations. These control stations should be located in each distinguishable cultural area throughout the state and should be numerous enough to adequately control all other blanket count stations. Location of control stations is of tantamount importance since traffic data secured at these stations will serve as a factor of interpolation with respect to rural traffic movement on primary roads as well as on secondary roads and will provide the basis for estimating an annual twenty-four hour traffic movement on every mile of road in the entire highway system.

Origin-Destination Study

Knowledge of the characteristics of road use on various types

of roads is of import, as well as knowledge of the amount of traffic moving over these roads. Compilation of this data will permit us to visualize the extent of general and local usage of, and the degree of urban and rural interest in various roads and classes of roads.

Origin-destination studies can only be secured by stopping vehicles at selected points of intersection on secondary as well as primary roads. This information shall be secured on secondary roads by the blanket count station recorder, as described in the preceding section. All types of motor vehicles shall be stopped and the driver interrogated in order that the required information may be obtained to properly fill out Form HPST-17 (see sample form). Origin-destination data should be obtained on primary roads only at loadometer stations, since the party operating these stations is sufficiently staffed and equipped to stop traffic without creating a hazard. However, direct questioning of drivers will usually not be attempted on primary roads unless traffic is light; instead, each vehicle will be stopped and each driver given a franked and self-addressed questionnaire card (see Form HPST-24), which he will be requested to fill out and mail. Distribution of these cards shall be made during daylight hours only.

Special origin-destination studies should also be conducted for the purpose of determining the feasibility of constructing alternate routes between certain points, by-pass or belt-line roads around certain cities, or improving existing unimproved routes. This information can only be secured by direct questioning of the traveling public at selected stations near these

points of contemplated change. Full dependence, however, should not be placed upon the data thus secured, since every new transportation facility generates new traffic which must be estimated on the basis of probable trade growth and related factors.

Automatic Counters

Continuous manual counts at key, loadometer and blanket count stations are necessarily impossible because of the exorbitant cost and it therefore becomes necessary to introduce another method of traffic tabulations which will be economically practicable. Uninterrupted recording of traffic can be done only by mechanical means and for this purpose an electrically controlled automatic counter has been developed by the Bureau of Roads for use on the Highway Planning Surveys. The Bureau has estimated that thirty-three such counters can be operated for the cost of one continuous manual-count station.

Automatic counters, however, cannot give the complete information necessary to make a comprehensive study of highway utilization since they record only the number of vehicles and not the type of vehicle nor the direction of travel. It is, therefore, essential that the various kinds of stations, already explained, be operated in order that a co-ordinated traffic movement pattern may be constructed from the data recorded at each type of station. Since most of the automatic counters and all of the key stations are located on main highways, it is important that the counters be installed as close to key stations as possible so that a relationship can be established between the classified manual count and the purely numerical automatic count.




FIGURE 4.- PROPOSED LAYOUT OF AUTOMATIC TRAFFIC-COUNTER INSTALLATION

Most of the automatic counters should be installed on main highways in order that various traffic movement characteristics may be ascertained at locations near large cities; at considerable distances from these cities; on tourist routes; and on principal industrial and agricultural routes. A few secondary-primary road intersections which provide a stable secondary road traffic pattern should be selected as locations for a few automatic counters, so that hourly traffic fluctuations between primary and secondary roads may be determined.

The automatic counter is electrically controlled and consists of two units installed on opposite sides of the road. One unit, producing the light source, projects two beams of light, thirty-one inches apart, across the road at an angle of twenty-three degrees. The other unit consists of two photoelectric cells connected with the counting mechanism. The light source beams are focused upon the photo-electric cells and when both beams are interrupted simultaneously, by passing vehicles, the photo-electric relay is actuated, thereby operating the recording mechanism. (see sketch)

Since both beams must be interrupted, pedestrians cannot be recorded. The light beams are rendered practically invisible by installing infra-red filters in the light source unit thereby eliminating any hazard or annoyance to motorists.

The record is printed on standard adding machine paper registering the accumulated total each hour on the hour. The day and the hour is printed on the paper and post-meridian time is indicated by a dash under the hour figure. Minutes are not registered except when the mechanism stops recording altogether

because of power failure or other reasons, thereby providing means for estimating, by interpolation, the number of vehicles which passed the recorder during the period of interruption.

The counter shall be inspected at irregular intervals and a manual shall be made and compared with the mechanical count. The tape record shall be removed for each ten-day period and inspected for power or mechanical failures in order that the time, duration and type of failure may be investigated. This information shall be officially recorded on Form HPST-26 (see sample form).

Weight Data

Detailed information pertaining to all types of trucks and busses travelling on main roads throughout the state will be obtained at loadometer and pit-scale weight stations. The method of operation and the character of the information varies so that it becomes necessary to describe each type of station separately.

Loadometer Stations

This type of station shall be operated as a key as well as a loadometer station and the location shall be selected in the same manner as was the key station, previously explained. Each loadometer circuit shall consist of eighteen stations; the number of circuits depending upon the number and extent of main routes within a state, and the apparent movement of load-bearing vehicles travelling over these routes. Georgia has three such circuits, making a total of fifty-four loadometer stations throughout the State. Operation of the full eighteen stations constitutes a cycle and each cycle shall be scheduled so that every station will be operated fourteen times, on alternate eight-hour shifts, throughout the period of a full year. The



Once Important Farm to Market Road
Virtually Abandoned by Relocation

hours of duty shall be the same as for key station recorders.

One day loadometer party shall be assigned to each of the three circuits and one night party, operating from 10:00 P.M. to 6:00 A.M., shall be assigned to cover all three circuits. The loadometer party shall be composed of a chief of party, recorder, weighman, traffic officer and a key station recorder, and shall be equipped as follows:

1. Automobile (Station Wagon)
2. Loadometer scale (portable)
3. Wooden loadometer pits
4. Flags with standards
5. Signs with standards
6. Lanterns
7. Flambeaux
8. Flashlights
9. Level (carpenter)
10. Pick, shovel and axe
11. Clip boards (18" x 24")
12. Forms HPST-11, 18, 20, and 25 (see sample forms)
13. Complete set of station sketches (see sample sketch)
14. Master schedule of operations
15. Order of leg operation at each station
16. Stationery and pencils

The loadometer shall be tested for accuracy at frequent intervals by placing it upon an accurate pit scale and weighing a truck simultaneously with the pit scale, in order that a precise comparison may be obtained. The results of this test shall be officially recorded upon Form HPST-25 (see sample form).

A location on the leg of the intersection of the station to be operated shall be selected with regard to safety of the party personnel and the motoring public. A pit shall be dug on the shoulder of the road on each side for the wooden pit boxes to fit into. The depth shall be such that the top of the loadometer, resting in the wooden pit boxes, shall be level with the surface of the road at axle length distance from the loadometer. All protective devices shall be placed at their respective positions. The traffic officer shall stop all trucks and busses and instruct the driver to proceed slowly to the loadometer where the chief of party shall direct him further. Since the loadometer can only weigh one wheel at the time, the party chief shall direct the driver how to proceed, and the weighman shall slide the loadometer directly under the wheel as it approaches the pit. While the party chief is questioning the driver, the weighman shall secure other information directly from the vehicle itself. In case a truck or bus is weighed empty, Form HPST-20a (see sample form), shall be filled out and pasted on the windshield, so that the next time this truck is stopped, it need not be weighed again if empty, but if loaded, then the truck or bus should be weighed and recorded and this empty weight recorded along with the loaded weight in order to determine the carried load.

All information secured at loadometer stations shall be listed on Form HPST-18 (see sample form), directly as called for, or by symbols in its respective column as follows:

1. Local, or nearest foreign state, if more than one license plate is displayed

2. Obtained from license tag

3. Obtained from license tag

Indicate total number of tags displayed

4. Type of vehicle to be indicated by the following symbols:

TK - Truck

TR - Trailer

TT - Tractor truck

ST - Semitrailer

Bus - Bus

Indicate total number of trailers

5. Type of body to be indicated by the following symbols:

Bus - Bus

CO - Covered, box, closed, delivery, panel, screen,
van

PL - Platform, flat bed

ST - Stake, crate, rack

TA - Tank

OP - Open, dump, pick-up

Pass- Passenger car used as bus or truck

Ref - Refrigerator

AC - Auto carrier

CH - Chassis only

BL - Not classified above

6. Operating classifications to be symbolized by:

P - Private truck

A - Common carrier truck engaged in intrastate or
interstate commerce and operating over a fixed
route

B - Common carrier truck engaged in intrastate or interstate commerce but not operating over a fixed route


E - Contract carrier truck engaged in intrastate or interstate commerce

S - School bus


A-1 - Common carrier bus engaged in intrastate or interstate commerce and operating over a fixed route

O - All others

7. Manufacturer's rated capacity to be obtained from plate, license tag, or by estimation, appending the letters P, L, and E respectively. Maximum gross load to be taken from caution plate or if vehicle carries no caution plate then record serial number
8. Respective wheel loads as indicated on loadometer scale
9. Double the sum of all wheel loads
10. Empty weight secured from empty weight sticker (see Form HPST-20a)
11. Difference between loaded weight and empty weight
12. Place where vehicle is owned or usually garaged
13. Place from where this particular trip was started
14. Final destination of trip
15. Total mileage including side trips, if any
16. Complete description of type of origin
17. Complete description of type of destination
18. Detailed description and amount of commodity carried, if truck, and number of passengers, if bus. If the vehicle is empty it should be so noted.



Location Sketch of Loadometer Station



Location Sketch of Key Station

Care shall be exercised in obtaining and recording all information since the data on each truck and bus is used in compiling statistics for the state as a whole. Reports shall be checked and mailed at the end of each operation so that computations may be carried forward progressively.

Pit Scale Stations

Pit scale stations shall be permanently located entirely off of the road near the edge of the right-of-way. The locations shall be on heavily traveled routes with a clear sight distance in both directions of one thousand feet or more. Four stations, in various sections of Georgia, shall be operated in rotation by one party in cycles of thirty days for each station. Trucks and busses travelling in one direction shall be stopped and weighed during a period of fifteen operating days and those travelling in the opposite direction shall then be stopped and weighed during the remaining fifteen days of the thirty day cycle. The hours of operation for the fifteen days shall be from 6:00 A.M. to 2:00 P.M. for five days; from 2:00 P.M. to 10:00 P.M. for five days; and from 10:00 P.M. to 6:00 A.M. for the remaining five days.

The party personnel shall consist of a chief of party, weighman, recorder, and traffic officer. The equipment shall consist of that issued to the loadometer party except that no loadometer will be used and that the following kind of forms and additional equipment will be issued.

Forms HPST-19 and 20b (see sample forms)

Fifty foot metallic tape, divided into feet and tenths of a foot, for measuring the length and width of each vehicle

and the wheel base length of each vehicle

Special level rod, divided into feet and tenths of a foot,
for measuring the height of vehicles

Each truck and bus, as it is weighed, shall be measured to determine the overall length, width, and the height of the vehicle, including the load, and the length of the wheel base. The driver of each vehicle shall be questioned by the chief of party to obtain all pertinent data required to properly fill out Form HPST-19.

All information secured at pit scale stations shall be recorded on Form HPST-19 (see sample form), directly as called for, or by symbols in its respective column as follows:

1-3. Same instructions as described for columns 1-2-3 on
Form HPST-18

4. Trade name of vehicle and year of manufacture

5-8. Same instructions as described for columns 4-5-7-18
on Form HPST-18

9. Tire equipment to be symbolized as follows:

For tractor truck or full trailer:

PP - two axle vehicle, single pneumatic tires,
front and rear

PPD - three axle vehicle, single pneumatic tires on
two front axles and dual pneumatic tires on
rear axle

PPP - three axle vehicle, single pneumatic tires on
all axles

PDP - three axle vehicle, single pneumatic tires on
front and rear axle, and dual pneumatic tires
on second axle

- PD - two axle vehicle, single pneumatic tires on front axle and dual pneumatic tires on rear axle
- PDD - three axle vehicle, single pneumatic tires on front axle and dual pneumatic tires on other two axles
- PS - two axle vehicle, pneumatic tires on front axle and solid tires on rear axle
- PSS - three axle vehicle, pneumatic tires on front axle and solid tires on other two axles
- SS - two axle vehicle, solid tires on both axles
- SSS - three axle vehicle, solid tires on all axles

For semitrailer:

- P - one axle semitrailer, single pneumatic tires
- D - one axle semitrailer, dual pneumatic tires
- S - one axle semitrailer, solid tires
- PP - two axle semitrailer, single pneumatic tires on both axles
- PD - two axle semitrailer, single pneumatic tires on front axle and dual pneumatic tires on rear axle
- DP - two axle semitrailer, dual pneumatic tires on front axle and single pneumatic tires on rear axle
- DD - two axle semitrailer, dual pneumatic tires on both axles
- SS - two axle semitrailer, solid tires on both axles

10. Indicate size of tires on each axle
11. Leave blank, to be filled in from test data
12. Maximum overall width of vehicle or load
13. Maximum overall length of vehicle or load

Overall distance from center of front axle to center of rear axle, indicate distance between dual axles, if any

14. Maximum overall height of vehicle or load
- 15-19. Record registered weight of each axle
20. Sum of all axle weights if truck or bus is loaded
21. Sum of all axle weights if truck or bus is empty
22. Difference between loaded weight and empty weight
23. Combined weight of tractor truck, semitrailer, and trailers
24. Enter axle number carrying maximum load
25. Leave blank, to be filled in later
26. Compute ratio of maximum loaded axle to total load

Trucks and busses weighed when empty shall have pit scale empty-weight sticker (see Form HPST-20b) affixed to their windshields, but if this same vehicle passes the station, carrying a load, it shall be weighed and recorded, and the empty weight shall be noted in column twenty-one. Empty vehicles which display a loadometer empty-weight sticker (see Form HPST-20a) shall be weighed on the pit scale and shall have the loadometer empty-weight sticker replaced with a pit scale empty-weight sticker. No vehicle shall be weighed more than once loaded and once empty during each five day period.

Form HPS T-11

Signed _____
Party Chief or Recorder.

Form HPS T-24

[illegible]

SHEET NO. 1 OF 1 SHEETS. CYCLE NO. 6
DISTRICT NO. 1 COUNTY Whitfield 155
WEATHER Clear 2 PM to 3 PM - Cloudy 3 PM to 5 PM - Rain 5 PM to 10 PM
PARTY NO. DL-1 TOTAL VEHICLES RECORDED 1768

STATE HIGHWAY BOARD OF GEORGIA
DIVISION OF HIGHWAY PLANNING SURVEY
IN COOPERATION WITH UNITED STATES BUREAU OF PUBLIC ROADS
DAILY DENSITY REPORT

DATE Feb. 18, 1938 DAY Friday
HOUR PERIOD OF COUNT: FROM 2 PM TO 10 PM STATION NO. 16
() DAYLIGHT SAVING TIME (x) KEY STATION
(x) CENTRAL STANDARD TIME () BLANKET COUNT CONTROL STATION
() EASTERN STANDARD TIME () BLANKET COUNT PRIMARY STATION
() BLANKET COUNT LOCAL STATION

HOURS	HORSE DRAWN VEHICLES	PEDESTRIANS	MOTORCYCLES	BICYCLES	LOCAL VEHICLES												FOREIGN VEHICLES														TOTAL VEHICLES (MOTOR VEHICLES ONLY)	HOURLY TOTALS (MOTOR VEHICLES ONLY)	Defective	
					PASSENGER CARS		TRUCKS						Tractor-Truck SEMI-TRAILER	TRUCKS WITH TRAILERS	BUSES		PASSENGER CARS		TRUCKS						Tractor-Truck SEMI-TRAILER	TRUCKS WITH TRAILER	BUSES							
					WITH TRAILER	WITHOUT TRAILER	MANUFACTURERS RATED CAPACITY IN TONS								WITH TRAILER	WITHOUT TRAILER	MANFRS. RATED CAPACITY IN TONS																	
							LIGHT		MEDIUM		HEAVY						LIGHT		MEDIUM		HEAVY													
							House	Other	Under 1 1/2	1 1/2	Over 1 1/2 Under 3	3 And Under 5					5	Over 5	Under 1 1/2	1 1/2	Over 1 1/2 Under 3	3 And Under 5	5	Over 5										
(1)	(2)	(3)	(4a)	(4b)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(14)	(15)	(16)	(17)	(18)	(19)	(20)	(21)	(22)	(23)	(24)	(25)	(26)	(27)	(28)	(29)	(30)	Front	Rear		
ROUTE NO. U.S. #41 - Ga. #3 TO Dalton DIRECTION FROM STATION East (Asphalt - Good Condition)																																		
2-3						15	15	1	6	1			2			1	2		40	40	1	3							72	58				
3-4						21	21	2	6	1			1			1	0		23	23	1	3							104	80				
4-5						29	29	2	7	1			1			1	1		52	52	1	3							184	156				
5-6						31	31	2	4	0			1			2	2		36	36	2	3							84	72				
6-7						20	20	3	4	1			1			1	1		48	48	3	0							71	67				
7-8						40	40	3	5	0			1			0	0		24	24	1	2							55	55				
8-9						38	38	5	6	1			1			1	1		21	21	1	1							34	39				
9-10						28	28	2	2	0			0			1	1		11	11	0	0							48	32				
TOTAL						357	357	30	62	13	0	0	20	0	4	10	8	2	344	3	22	3	0	0	0	0	0	0	878	878	4	5		
ROUTE NO. Ga. #2 TO La Fayette DIRECTION FROM STATION South West (Gravel - Good Condition)																																		
2-3						2	2	1	1																				3	1				
3-4						3	3		1							2		1	1										7	7				
4-5						2	2									1													5	5				
5-6						5	5	1	1							1		1	1										2	2				
6-7						1	1	2					1																7	7				
7-8						4	4	1	1																				5	5				
8-9						5	5	1	1																				4	4				
9-10						1	1	2	1																				2	2				
TOTAL						36	36	9	5	0	0	0	1	0	4	0	0	0	2	0	0	0	0	0	0	0	0	0	57	57	0	1		
ROUTE NO. U.S. #41 - Ga. #3 TO Ringgold DIRECTION FROM STATION West (Asphalt - Good Condition)																																		
2-3						19	19	1	6	0			1			1	0	1	23	23	1	2							55	51				
3-4						15	15	1	4	0			1			1	0	40	40	1	3								71	74				
4-5						23	23	2	4	1			1			1	1	35	35	0	2								102	68				
5-6						27	27	2	8	1			1			1	1	52	52	1	5								143	131				
6-7						35	35	2	6	0			1			1	1	24	24	0	0								75	66				
7-8						14	14	1	4	1			1			1	1	47	47	3	2								31	31				
8-9						28	28	3	6	1			1			1	1	22	22	3	1								45	45				
9-10						35	35	3	6	1			1			1	1	21	21	1	1								55	55				
TOTAL						325	325	21	65	13	0	0	19	0	0	10	8	2	342	3	22	3	0	0	0	0	0	0	833	833	4	4		
ROUTE NO. TO DIRECTION FROM STATION																																		
2-3																																		
3-4																																		
4-5																																		
5-6																																		
6-7																																		
7-8																																		
8-9																																		
9-10																																		
TOTAL																																		

TRIP CLASSIFICATION REPORT

Loadometer Station

1 NO TION	2 Type of Vehicle	3 PLACE OF OWNERSHIP					4 TRIP ORIGIN						5 TRIP DESTINATION						6 Trip Classification	7 TRIP INFORMATION									
		a		b	c	d	e	f	a		b	c	d	e	f	g	a			b	c	d	e						
		IN OR NEAR	Dist. in Miles	Direc- tion	POP. GROUP	CITY OR TOWN	COUNTY	State	IN OR NEAR	Dist. in Miles	Direc- tion	POP. GROUP	CITY OR TOWN	COUNTY	State	TYPE	IN OR NEAR	Dist. in Miles		Direc- tion	POP. GROUP	CITY OR TOWN	COUNTY	State	TYPE	VIA PLACES & ROUTES	Miles	Time	No. Persons or Commodities Carried
	P	3	S		Taylorsville	Bartow	Ga.	3	S		Taylorsville	Bartow	Ga.	In		Fairmount	Gordon	Ga.							Ga.#113-61	35	1-10	3	Social
	T	5	W		Euharlee	Bartow	Ga.	5	W		Euharlee	Bartow	Ga.	In		Cartersville	Bartow	Ga.							Co. Rd. Ga.#61	12	0-30	Furniture	Business
	B	In			Cartersville	Bartow	Ga.	2	E		Stilesboro	Bartow	Ga.	In		Cartersville	Bartow	Ga.							Co. Rd. Ga.#61	8	0-40	14	Business
	T	In			Ladds	Bartow	Ga.	In			Ladds	Bartow	Ga.	In		Rockmart	Polk	Ga.							Ga.#61-113	20	0-50	Cotton	Business
	P	In			Rockmart	Polk	Ga.	In			Rockmart	Polk	Ga.	In		Blue Ridge	Fannin	Ga.							Ga.#113-61 -53-5	96	3-40	1	Pleasure

Herbert R. Jacobson
District Supervisor

Sheet No. 1 of 4 Sheets Cycle No. 6
District No. 1 County Whitfield 155
Route No. 41 3 Name Number
Party No. DL-1 U.S. State
Official Visitors H. R. Jacobson Total Vehicles Recorded 75
Name Hours of Visit 2-3:15

STATE HIGHWAY BOARD OF GEORGIA
DIVISION OF HIGHWAY PLANNING SURVEY
IN COOPERATION WITH UNITED STATES BUREAU OF PUBLIC ROADS
Daily Truck and Bus Loadometer Report

Station No. 16 (Leg #1) Direction from Station S.E. (1 Mile)
Date Feb. 18, 1938 Day Friday
Hour Period of Count: From 2:00 PM To 10:00 PM Weather Cloudy 2-5
[] Daylight Saving Time Checked by R. L. Randolph Signed C. Green
[x] Central Standard Time Chief of Party Recorder
[] Eastern Standard Time Approved: Herbert R. Jacobson
District Supt.

ROAD SECTION	1	2	3		4		5	6		7			8		9	10	11	12			13		14			15		16	17	18							
	STATE OF REGISTRATION	REGISTRATION CLASS	LICENSE NUMBER	NO. OF TAGS	TYPE OF VEHICLE	NO. TRAILERS	TYPE OF BODY	Operating Classification		Manufacturers Rated Capacity or Pay Load Tons or Pounds or No. of Pass.	Maximum Gross Load Tons or Pounds or No. of Pass.	Axle Arrangement	WHEEL LOAD			Max. Axle	LOADED WEIGHT	EMPTY WEIGHT	CARRIED LOAD	TOTAL WEIGHT OF COMBINATION			ORIGIN		DESTINATION			TRIP		TYPE OF ORIGIN	TYPE OF DESTINATION	COMMODITIES CARRIED	NUMBER OF PASSENGERS				
								Licensed For	Used For				AXLE 1	AXLE 2	AXLE 3					In or Near	CITY	COUNTY	State	In or Near	CITY Or TOWN	COUNTY	STATE	In or Near	CITY Or TOWN					COUNTY	STATE	Classification	MILEAGE
	Ohio	R	6295	1	TK O	ST	P	P	1 1/2 P	11550			1900	6600			17000				In Muncie	Lucas	O	In Tampa	Hillsboro	Fla	In Muncie	Lucas	O	1200	Fruit Packing Hse	Whse. Prod. Market	Oranges				
	Ga.	1 1/2 E	85103	2	TT 1	CH	A	A	1 1/2 L	13000			1700	5500							In Atlanta	Fulton	Ga.	In Atlanta	Fulton	Ga.	In Chattanooga	Hamilton	Tenn	122	Freight Terminal	Freight Terminal	Mixed Freight				
	Ga.	3 1/2 E	343	3	ST O	CO	A	A	5 E	15000					6000		26400																				
	Ga.	C	33	3	Bus O	Bus	A-1	A-1	35	Plate Cov.			4600	7800			24800				In Jacksonville	Duval	Fla.	In Jacksonville	Duval	Fla.	In Chattanooga	Hamilton	Tenn	446	Bus Terminal	Bus Terminal		17			
	Tenn	2	22744	1	TK O	ST	P	P	1 1/2 E	Int. # 27261			1900	5100			14000				In Fayetteville	Lincoln	Tenn	In Fayetteville	Lincoln	Tenn	In Atlanta	Fulton	Ga.	223	Stock Barn	Stock Yard	38 Calves				
	Ga.	1 1/2 A	5531	1	TK O	TA	P	P	1 1/2 L	9300			1500	3700			10400	4800	5600		In Dalton	Whitfield	Ga.	In Dalton	Whitfield	Ga.	In Tunnel Hill	Whitfield	Ga.	9	Whse. Gas. Plant	Retail Gas. Station	620 gal. gas. 26 gal. oil				
	Ga.	1 1/2 B	35004	4	TT 1	CH	A	A	2 P	12215			1600	6200							In Nashville	Davidson	Tenn	In Jacksonville	Duval	Fla.	In Nashville	Davidson	Tenn.	584	Decks	Whse. Grocery Co.	Sugar in Bags				
	Ga.	3 1/2 E	3196	4	ST O	CO	A	A	4 E	18000					5400		26400	11040	15360																		
	Ky.	L	8511	1	TK O	ST	P	P	1 1/2 E	4600			1200	1800	1600		9200				In Campbellville	Taylor	Ky.	In Atlanta	Fulton	Ga.	In Campbellville	Taylor	Ky.	403	Granite Shed	Granite Shed	Block Granite				
	Ill.	F	5165	1	TK O	ST	P	P	1 1/2 E	9300			2000	6200			16400				In Chicago	Cook	Ill.	In Atlanta	Fulton	Ga.	In Chicago	Cook	Ill.	725	Whse. Prod. Market	Whse. Prod. Market	Onion Sets				

Sheet No. 1 of 5 Sheets.
 District No. 1 County Cobb Name 033
 Route No. 41 U.S. 3 State Georgia
 Party No. 1 Total Vehicles Recorded 63
 Official Visitors H. R. Jacobson 6:15 - 7:30
 Name Hours of Visit

STATE HIGHWAY BOARD OF GEORGIA
 DIVISION OF HIGHWAY PLANNING SURVEY
 IN COOPERATION WITH UNITED STATES BUREAU OF PUBLIC ROADS
 DAILY TRUCK AND BUS PIT-SCALE REPORT

Station No. 1 Direction N Bound Traffic
 Date Feb. 23, 1938 Day Wednesday
 Hour Period: From 2PM To 10PM Weather Cloudy
 [] Daylight Saving Time Signed By J. Johnson Recorder
 [x] Central Standard Time Checked By S. D. Murphy Party Chief
 [] Eastern Standard Time H. R. Jacobson Dist. Supervisor

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26			
State of Registration	Registration Class	License Number	No. of Tags	Make and Year	Type of Vehicle	No. of Trailers	Type of Body	Manufacturers Rated Capacity or Seating Capacity Tons or Lbs. or No. of Persons	Manufacturers Gross Weight Rating	Commodities Carried or Number of Passengers	Tire Equipment	Tire Size in Inches	Tire Carrying Capacity	Overall Width in Feet and Tenths	Length Overall Feet and Tenths	Wheel Base Feet and Tenths	Maximum Height Feet and Tenths	Vehicle Loads and Weights										
																		Axle No. 1	Axle No. 2	Axle No. 3	Axle No. 4	Axle No. 5	Loaded Weight	Empty Weight	Carried Load	Total Train Weight	Maximum Axle Weight	Ratio of Max. Axle Weight to Total Load
Ga.	1 1/2 B	85103	2	Chev. 36	TT	1	CH	1 1/2 L	13000	Mixed Freight	PD	36/8			36.2	27.5		3400	11000									
Ga.	3 1/2 E	343	3	Hobbs 35	ST	0	CO	5 E	15000		DD	36/8		7.8			11.9			12000			26400			26400	3	.45
Tenn.	2	22744	1	Int. 37	TK	0	ST	1 1/2 E	Serial No. 27261	38 Calves	PD	36/8		7.5	23.3	13.2	10.6	3800	10200				14000			14000	2	.73
Ga.	1 1/2 B	35004	4	Chev. 37	TT	1	CH	2 P	12215	Sugar in Sacks	PD	40/8			36.3	27.5		3200	12400									
Ga.	3 1/2 E	3196	4	Freuhauf 36	ST	0	CO	4 E	18000		DD	40/8		7.6			11.7			10800			26400	11040	15360	26400	2	.47

Loadometer Station

Empty Weight Sticker

Form HPS T-20a

Form HPS-T-20a LOADOMETER STATION No.

STATE HIGHWAY BOARD OF GEORGIA
DIVISION OF HIGHWAY PLANNING SURVEY

In cooperation with U. S. Bureau of Public Roads

State.....License No.....

EMPTY WEIGHT.....POUNDS

*Defacement or Removal of this Sticker
Will Require Reweighing of Vehicle*

Pit Scale Station

Empty Weight Sticker

Form HPS T-20b

Form HPS-T-20b PIT SCALE STATION No.

STATE HIGHWAY BOARD OF GEORGIA
DIVISION OF HIGHWAY PLANNING SURVEY

In cooperation with U. S. Bureau of Public Roads

State.....License No.....

EMPTY WEIGHT.....POUNDS

*Defacement or Removal of this Sticker
Will Require Reweighing of Vehicle*

STATE HIGHWAY BOARD OF GEORGIA
DIVISION OF HIGHWAY PLANNING SURVEY
In Cooperation with U. S. Bureau of Public Roads

LOADOMETER TEST SHEET

District No. 1 Party No. DL-1 Date January 5, 1938
Location of Test (Place) Intersection of Ga. #12
& East Atlanta Road Ga. Owner of Scales DeKalb County

1. Loadometer No. 4141

Weight of Wheel No. 1, Right:	<u>800</u>	Left:	<u>800</u>
Weight of Wheel No. 2, Right:	<u>800</u>	Left:	<u>800</u>
Weight of Wheel No. 3, Right:	<u> </u>	Left:	<u> </u>
Total Wheel Weight, Right:	<u>1600</u>	Left:	<u>1600</u>

Total Weight of Vehicle by Loadometer 3200Total Weight of Vehicle by Scales(Pit) 3180No. Pounds Loadometer Off (Show plus
or minus) 202. Loadometer No.

Weight of Wheel No. 1, Right:	<u> </u>	Left:	<u> </u>
Weight of Wheel No. 2, Right:	<u> </u>	Left:	<u> </u>
Weight of Wheel No. 3, Right:	<u> </u>	Left:	<u> </u>
Total Wheel Weight, Right:	<u> </u>	Left:	<u> </u>

Total Weight of Vehicle by Loadometer Total Weight of Vehicle by Scales(Pit) No. Pounds Loadometer Off (Show plus
or minus) Signed by: R. L. Randolph
(Chief of Party)Approved: Herbert R. Jacobson
(District Supervisor)

STATE HIGHWAY BOARD OF GEORGIA
DIVISION OF HIGHWAY PLANNING SURVEY
In Cooperation with U. S. Bureau of Public Roads

Cartersville, Georgia

February 24, 1938

Mr. O. T. Ray, State Director
Highway Planning Survey
301-306 Bona Allen Building
Atlanta, Georgia

Re: Automatic Traffic Recorder No. 1
Located 5 Miles NW of Cartersville
(Direction) (Town or City)
Route No. - U. S. No. 41; Georgia, 3
Adjacent Key Station No. 255

Dear Sir:

I visited this recorder at 12:30 M, February 24, 1938. I am enclosing tape removed from recorder for period beginning 3:00 P M, February 14, 1938, and ending 1:00 PM Feb. 24, 1938.

Power failures were noted and exact time and durations were determined from the records of the public utility supplying power (or other reliable source) as follows: None

Equipment failures were as follows: (Show time, duration and type failures)

None

If bulbs were changed since last report indicate: Right: No
(Date)
Left: No
(Date)

Remarks: Manual count made from 12:30 PM to 1:00 PM and compared
with automatic count. Results checked.

Yours very truly,

Herbert R. Jacobson
(Name)

District Supervisor
(Title)

encl.

PART V

FINANCIAL SURVEY

Financial Survey

The financial survey embraces a detailed study and analysis of income and expenditures of all governmental units within the state; the relative use of the various types of roads; and the future allocation of public tax money for highway improvements. The entire financial study is divided into three sections as follows:

1. Fiscal Survey
2. Road Use Survey
3. Motor Vehicle Allocation Survey

Fiscal Survey

The purpose of the fiscal survey is to thoroughly study and analyze the tax structure of the entire state in order to estimate the financial resources which will be available for investment in a highway program of the future. To this end, a knowledge of all highway tax resources; Federal, State, County and Municipal, is essential. Due to the overlapping of receipts and expenditures in all units of government and the need for a comparative study of all taxes, it is impossible to segregate the study of highway tax resources without also studying the entire tax structure of the State.

The study of all tax records shall extend over the period of one calendar year, preferably the year just ended. The units of government to be studied shall be the State, the Counties, the Municipalities, and their respective Boards of Education; and any other units of government such as special highway districts, drainage districts, and independent school districts. The population figures published by the United States Bureau of Census,

shall be used as the basis for dividing all governmental units into two general classes, namely, rural areas and urban places. These two general classes shall in turn be subdivided into the following population groups:

Unincorporated Areas

Class A - 2500 or more and population density of 1000 or more per square mile

Class B - All other unincorporated areas

Incorporated Places

Class 1A - 1000 and under

Class 1 - 1001 to 2500

Class 2 - 2501 to 5000

Class 3 - 5001 to 10000

Class 4 - 10001 to 25000

Class 5 - 25001 to 50000

Class 6 - 50001 to 100000

Class 7 - 100001 to 250000

Class 8 - 250001 to 500000

Class 9 - 500001 to 1000000

Class 10 - Over 1000000

All data shall be obtained from existing records of the year under study in each of the governmental units. The duty of collecting this data shall be performed by ten field auditors whose sole duty is to report all tax receipts and expenditures, as recorded, regardless of personal opinion as to their validity or the method of accounting. Only when all field auditing has been completed and a comparative study has been made of all units of government will it be feasible or advisable to criticize discrepancies or suggest changes in the method of accounting.

Tabulation of financial data shall be made on Form FS-1 (see sample form). This form is divided into three sections which shall be used for the following tabulation purposes:

- Section 1 - Show total receipts for current and non-current, local and non-local purposes in their respective columns and according to the source of revenue.
- Section 2 - List all commitments, according to the source of revenue, segregating those legally restricted to the payment of debt principal from those specifically allocated for other governmental units and not currently available for local purposes.
- Section 3 - Tabulate all funds according to the source of revenue which are available for all local current and non-current purposes.

Tabulation of all financial data shall be done with respect to the various sources of revenue. These sources of revenue are listed in the column headed 'Items', and are to be determined in accordance with the following explanation:

1. Total tax levies is the summation of general property levies and special assessments.
2. The general property tax pertains to the direct tax on real and personal property located within a general tax district and imposed at a uniform rate, but should not include the tax imposed on motor vehicles.
3. Special assessments are those levies exacted to defray the cost of specific improvements and are based upon

the assumption of increased value on property affected by these improvements. A special assessment differs from a general property tax, in that the former is levied upon a specific group of properties, whereas, the latter is levied upon a general class of individual properties at a uniform rate.

4. The total property tax collections is the sum of the general tax and the special assessment collections.
5. Total general tax collections is the sum of collections received from the current and delinquent property tax.
6. The current general property tax collection is the actual receipt of taxes levied within the base year.
7. Delinquent general property tax collections are those derived from delinquencies of payment.
8. Special assessments are those total collections of this type of taxes, current and delinquent.
9. Other local revenues is the total of motor vehicle and other special imposts and all other general revenues.
10. Motor vehicle imposts are local taxes levied against ownership and operation of motor vehicles.
11. Other special imposts are those collected from special local tax levies.
12. Other general revenues include all earnings accrued from interest, fees, fines, and profits on incomes derived from any public service enterprise.
13. Total local taxes and revenues is the sum of total property tax collections and other local revenues.
14. Total state-administered revenues is the sum of the

c

subventions, shared taxes, state-administered local taxes and special aids.

15. Subventions are the amounts of monetary assistance rendered by another governmental unit, regularly established and governed by specific enactments.
16. Shared taxes are those collected under state authority and distributed to local divisions without losing their identity. Subventions differ from shared taxes in that they bear no direct relationship to the amounts derived from the residents of any one particular unit of government.
17. Local taxes are those belonging strictly to a local unit of government but administered by the state.
18. Special aids are grants provided infrequently, by the state, for temporary or emergency needs.
- 19-23. The description set forth above for the state-administered revenues applies to county-administered revenues except for the unit of government administering the revenues.
24. Federal aids include all temporary or emergency aid received direct from the Federal Government, but does not include PWA and RFC loans which are to be shown as borrowings.
25. Total non-local taxes and revenues is the sum of total state-administered revenues, total county-administered revenues, and federal aids.
26. Total borrowings is the sum of temporary loans and bonds.

27. Temporary loans include all assumed floating and unfunded obligations.
28. Bonds include all incurred forms of bonded or fixed indebtedness.
29. Total current receipts is the sum of total local taxes and revenues, total non-local taxes and revenues, and total borrowings.
30. Decrease in balances is the item derived from an analysis of balances at the beginning and end of the year in order that total non-local taxes and revenues may equal the sum of net direct expenditures, total debt retirements, aids and grants paid, and increase in balances.
31. This total is the sum of total current receipts and decrease in balances.
32. Direct expenditures, other than interest, are the total amounts expended by governmental units for current purposes including those allocated to other units of government, but excluding aids and grants.
33. Temporary loan interest paid is the interest paid on all floating and unfunded obligations.
34. Bond interest paid is the interest paid on bonded or fixed indebtedness.
35. Gross direct expenditures is the sum of the direct expenditures other than interest, temporary loan interest paid, and bond interest paid.
36. Deductions from gross expense include non-governmental deductions, which are commercial earnings accruing

from the sale of materials or services in excess of public requirements, and governmental deductions, which result from contractual agreements whereby one unit of government performs services or furnishes goods to another.

37. Net direct expenditures is the difference between gross direct expenditures and the deductions from gross expenditures.
38. Total debt retirement is the sum of temporary debt and bonded debt retirements.
39. Temporary debt retired is the amount of unfunded or floating obligations retired.
40. Bonded debt retired is the amount of bonded or fixed indebtedness retired.
41. Aids and grants paid include all financial assistance to other governmental units.
42. Total current expenditures is the sum of the net direct expenditures, total debt retirements, and aids and grants paid.
43. Increase in balances is the item used to balance Item 31 with Item 44 in order that these two items may be equal.
44. Total is the sum of total current expenditures and the increase in balances. This amount should balance with Item 31.
45. Total debt service is the sum of the interest paid on temporary loans, the interest paid on bonds, and the total debt retirements.

46. Total debt outstanding is the sum of outstanding temporary and bonded debts.
47. Temporary debt outstanding includes all outstanding unfunded or floating obligations.
48. Bonded debt includes all forms of outstanding bonded or fixed indebtedness.
49. Debt reserves include the book value of all sinking and debt retirement fund investments and the cash balance of such funds on hand.
50. Net debt is the difference between the total outstanding debt and the debt reserves.

Balances. The special schedule in the right hand corner of the form provides for a special analysis of balances to take care of various types of funds existing in any governmental unit.

All receipts shall be tabulated in their respective columns under the following main headings:

1. Highways
2. Other public functions
3. General fund
4. Grand total

Tabulation of these receipts shall indicate the amount legally allocated to each specific classification and to no other. No analysis will be attempted of receipts classified under the heading of General Fund.

Proper tabulation of receipts shall be based upon the following description of column classification:

- A. Construction covers the cost of additions and better-

ments to the highway system, including right-of-way purchases.

- B. Maintenance includes all expenditures necessary to preserve and keep each type of roadway structure and facility as nearly as possible in its original condition of construction, or improved to provide satisfactory service. Cost of maintenance should be separated as to maintenance of condition and maintenance of operation.
- C. Other highway expenditures includes all items of overhead. Cost of highway patrol and municipal traffic police shall be recorded separately from regular municipal or state police systems, in order to obtain a true estimate of such service.
- D. Total of all receipts listed under the main heading, 'Highways'.
- E. Education covers the cost of all educational facilities such as schools, libraries, and museums.
- F. Public welfare and services embraces all functions of general welfare such as personal and property protection, health and sanitation, conservation of natural resources, and charitable and recreational facilities.
- G. General government expenses cover the cost of the legislative, executive, and judicial functions of government.
- H. Total of all costs under the main heading, 'Other Public Functions'.
- I. General fund includes all receipts not specifically allocated to any other classification.
- J. Grand total of all expenditures listed.

Special analysis of Highway Finances:

It is necessary to give special consideration to the study of highway financial data in order to definitely determine the sources of revenue and expenditure. Sources of revenue shall be determined as coming from the following:

1. Taxes derived from motor vehicle registration fees and motor fuel taxes.
2. Property taxes, special imposts, subventions and aids, borrowings, reserves, and balances.

Expenditures shall be segregated as to primary, secondary, or tertiary systems, and shall be classified according to the following:

1. Road construction
2. Bridge construction
3. Right-of-way
4. Maintenance of condition
5. Maintenance of operation
6. Interest expense
7. Other

Road Use Survey

A road use survey provides the basis for determining the relative use of various roads and types of roads, by the residents of a state. The data compiled by this survey will be classified according to population groups and counties, showing not only the total mileage traveled on the various systems by vehicles registered in the state, but also the actual source of all traffic by these population groups and by counties. It will permit us to analyze the actual utilization by motorists of urban



Excellent Location with Respect to
Alignment, Grade and Visibility



Sharp Curve with Limited Sight Distance

and rural portions of the state highways, of county roads, and of city streets.

Several important factors of highway planning can be determined from this study, namely:

1. The total amount of travel on various roads, and types of roads in a given area.
2. The amount of travel on all highway systems of a state by vehicle owners residing in each distinctive type of locality.
3. Comparison of the total traffic carried by various types of roads and city streets, and the relationship of this traffic to the several systems.
4. Relationship between the individuals producing this traffic and those providing the revenues for building and maintaining the roads.

Information is obtained by personally interviewing representative car and truck owners throughout the state as to where, how far, and for what purpose they drove their vehicles during the preceding twelve month period. This same information should be obtained from commercial vehicle owners such as bus and truck operators. Selection of representative vehicle owners should be carefully made in order that the individuals, who are to be interviewed, may represent the various population classes, both urban and rural, and the various occupational classes.

A special interview form (see sample Form RU-1) shall be used in collecting information for the road use survey. The following information shall be obtained in order to properly fill out the form:

1. Purpose of travel and route followed. The purpose of

the trip shall be classified under the various subdivisions of business and pleasure as indicated on the form.

2. The number of round trips for each type of trip and the miles per round trip.
3. Total miles traveled in the state and out of the state for each type of travel.
4. Total miles traveled on primary state highways, on secondary highways, and on local roads and streets respectively. This total shall then be separated as to the amount of mileage traveled on strictly rural sections of the primary and secondary roads and the amount of mileage traveled on strictly township sections of the local roads and streets.
5. The name, postoffice and legal address, and occupation of the person interviewed.
6. Make, model, net weight or capacity, license fee paid, average miles per gallon, gallons of gasoline consumed in the state for each individual car or truck being operated.
7. Number of counties traveled in other than that of residence, number of other states traveled in, and the miles to farthest point of destination.
8. Distance the owner lives from a primary state highway, secondary highway, and township or county road.

Motor Vehicle Allocation Survey

The purpose of motor vehicle allocation studies is to secure and analyze information relative to the distribution or location of motor vehicles and to fees and fuel taxes paid by owners of

these vehicles so as to classify this information by counties, by rural and urban areas, and by population groups for urban areas.

The data necessary for an analysis of this study is obtained from all motor vehicle owners by means of questionnaire cards, Form HPS-325 and Form HPS-326 (see sample forms). These cards shall be filled in by the owners for every motor vehicle in their possession and shall contain the following information:

1. Type of vehicle
2. Place of ownership or headquarters for vehicle by county, city, or nearest city if outside of corporate limits
3. Make and year model of vehicle
4. Whether vehicle was new at time of purchase
5. Present speedometer reading
6. Total number of miles traveled during the year under study, and the number of miles traveled within the state under study
7. Average number of miles per gallon of gasoline
8. Whether mileage and gasoline consumption was obtained by estimate or from actual records
9. If a bus or truck, the amount of maintenance tag fee paid; the factory weight and seating capacity
10. Occupation of owner
11. If the vehicle is for hire or not in case it is a truck

Additional information, obtained from the various governmental units, will be necessary in order that accurate and complete information will be available for a comprehensive compilation of all data. The information obtained as a result of this study

shall be tabulated according to population group and type of vehicle into the following classification tables for the year under study:

1. Motor vehicle registration
2. State, county, local, and total motor vehicle imposts
3. State registration fees paid by owners of various types of vehicles
4. State motor fuel taxes paid by owners of various types of vehicles
5. Average number of miles traveled and gallons of gasoline consumed in state per vehicle
6. Average total number of miles traveled and gallons of gasoline consumed irrespective of the state under study
7. Average state motor fuel taxes and registration fees paid per vehicle
8. Frequency distribution of passenger cars and trucks according to miles traveled
9. Relation of annual average mileage travel and gasoline consumption as reported by vehicle owners on basis of estimates and actual records
10. Percentage distribution of passenger cars by weight classes
11. Percentage distribution of trucks by rated capacity
12. Registered vehicles classified according to average number of miles traveled by vehicles in each year model group
13. Average miles per gallon of gasoline consumed by passenger cars in different weight classes
14. Average miles per gallon of gasoline consumed by trucks

in different capacity classes

15. Percentage distribution of passenger cars and trucks according to year models
16. Average miles per gallon of gasoline consumed by light, medium and heavy passenger cars according to miles traveled
17. Average miles per gallon of gasoline consumed by trucks of various rated capacities according to miles traveled.

HIGHWAYS				OTHER PUBLIC FUNCTIONS				GENERAL FUND		GRAND TOTAL		COMMITMENTS								CURRENTLY AVAILABLE FOR LOCAL PURPOSES				
CONST.	MAINT.	OTHER	TOTAL	EDUCATION	PUBLIC WELFARE & SERVICES	GENERAL GOV'T	TOTAL			ITEM COMPOSITION	ITEMS	DEBT			FOR OTHER GOVERNMENTS			TOTAL		HIGHWAYS	OTHER	GENERAL FUND	TOTAL	
A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S		T	U	V	W	
										2 + 3	(1) TOTAL TAX LEVIES													
											(2) GENERAL PROPERTY													
											(3) SPECIAL ASSESSMENT													
										5 + 8	(4) TOTAL PROPERTY TAX COLLECTIONS													
										6 + 7	(5) TOTAL GENERAL													
											(6) CURRENT													
											(7) DELINQUENT													
											(8) SPECIAL ASSESSMENT													
										10 + 11 + 12	(9) OTHER LOCAL REVENUES													
											(10) MOTOR VEHICLE IMPOSTS													
											(11) OTHER SPECIAL IMPOSTS													
											(12) OTHER GENERAL REVENUES													
										4 + 9	(13) TOTAL LOCAL TAXES AND REVENUES													
										15+16+17+18	(14) TOTAL STATE-ADMINISTERED REVENUES													
											(15) SUBVENTIONS													
											(16) SHARED TAXES													
											(17) STATE-ADMINISTERED LOCAL TAXES													
											(18) SPECIAL AIDS													
										20+21+22+23	(19) TOTAL COUNTY-ADMINISTERED REVENUES													
											(20) SUBVENTIONS													
											(21) SHARED TAXES													
											(22) COUNTY-ADMINISTERED LOCAL TAXES													
											(23) SPECIAL AIDS													
											(24) FEDERAL AIDS													
										14 + 19 + 24	(25) TOTAL NON-LOCAL TAXES AND REVENUES													
										27 + 28	(26) TOTAL BORROWINGS													
											(27) TEMPORARY LOANS													
											(28) BONDS													
											(29) TOTAL CURRENT RECEIPTS													
											(30) DECREASE IN BALANCES													
										13+25+26+30	(31) TOTAL													
											(32) DIRECT EXPENDITURES OTHER THAN INTEREST													
											(33) TEMPORARY LOAN INTEREST PAID													
											(34) BOND INTEREST PAID													
										32 + 33 + 34	(35) GROSS DIRECT EXPENDITURES													
											(36) DEDUCTIONS FROM GROSS													
										35 - 36	(37) NET DIRECT EXPENDITURES													
										39 + 40	(38) TOTAL DEBT RETIREMENTS													
											(39) TEMPORARY DEBT RETIRED													
											(40) BONDED DEBT RETIRED													
											(41) AIDS AND GRANTS PAID													
											(42) TOTAL EXPENDITURES													
											(43) INCREASE IN BALANCES													
										37+38+41+43	(44) TOTAL													
										33 + 34 + 38	(45) TOTAL DEBT SERVICE													
										47 + 48	(46) TOTAL DEBT OUTSTANDING													
											(47) TEMPORARY													
											(48) BONDED													
											(49) DEBT RESERVES													
										46 - 49	(50) NET DEBT													

FUND	BALANCES			
	OPENING	CLOSING	INCREASE	DECREASE
HIGHWAY				
GENERAL				
ETC.				
BANKING FUND				

NO. _____

MILES TRAVELED BY MOTOR VEHICLE OWNERS

AND ROAD USE IN _____

[illegible]

NAME _____
P.O. ADDRESS _____

LEGAL RESIDENCE IN { TOWNSHIP _____
CITY _____
IN THE COUNTY OF _____
OCCUPATION _____

PASSENGER CAR MAKE _____ MODEL _____
MOTOR TRUCK MAKE _____ MODEL _____
NET WEIGHT _____ CAPACITY _____
LICENSE FEE PAID _____
AVERAGE MILES PER GALLON _____
GALLONS OF GAS CONSUMED IN STATE _____
DOES OWNER KEEP RECORDS ? _____

VEHICLE TRAVELED IN.....COUNTIES OTHER THAN THAT OF RESIDENCE
NUMBER OF OTHER STATES TRAVELED IN
FARTHEST DESTINATION WAS APPROXIMATELY..... MILES
DISTANCE OWNER LIVES FROM { PRIMARY STATE HIGHWAY
 { SECONDARY HIGHWAY
 { TOWNSHIP ROAD
REMARKS:.....
INTERVIEW SECURED BY..... DATE..... CHECKED BY.....

Motor Vehicle Allocation Survey

Questionnaire Card

Form HPS-325	DETACH AND MAIL	NO POSTAGE REQUIRED	
(Use this card for one vehicle only) (Check type of vehicle below)		LEAVE THIS COLUMN BLANK	
PASSENGER CAR <input type="checkbox"/> HEARSE <input type="checkbox"/> TAXI-CAB <input type="checkbox"/> AMBULANCE <input type="checkbox"/> BUS <input type="checkbox"/>			
1. HEADQUARTERS FOR ABOVE VEHICLE (Place where it is usually kept or garaged) (a) Name of County _____ (b) If within corporate limits of a City or Town, give name _____ (c) If outside corporate limits of a City or Town, check here _____			
2. GIVE MAKE _____ AND YEAR MODEL _____ OF VEHICLE YOU NOW OPERATE.			
3. DID YOU PURCHASE THIS VEHICLE NEW? _____			
4. PRESENT SPEEDOMETER READING _____ MILES			
5. GIVE MILES ABOVE VEHICLE WAS DRIVEN DURING 1937; OR IF YOU CHANGED VEHICLES DURING 1937 GIVE COMBINED TRAVEL FOR BOTH VEHICLES: (a) Total miles traveled regardless of States _____ (b) Total miles traveled in Georgia _____			
6. AVERAGE NUMBER OF MILES OBTAINED PER GALLON OF GASOLINE _____			
7. ARE THE ANSWERS TO QUESTIONS 5 AND 6 BASED ON: Estimates _____ or Records _____ (Check one)			
8. IF BUS, SHOW: \$ _____; _____; _____ Maintenance tag fee paid Factory Weight Seating Capacity			
9. WHAT IS YOUR OCCUPATION? _____			

Form HPS-325

Form HPS-326	DETACH AND MAIL	NO POSTAGE REQUIRED	
TRUCK <input type="checkbox"/> TRACTOR-TRUCK <input type="checkbox"/>		LEAVE THIS COLUMN BLANK	
(Use this card for one vehicle only) (Check type of vehicle)			
1. HEADQUARTERS FOR ABOVE VEHICLE (Place where it is usually kept or garaged) (a) Name of County _____ (b) If within corporate limits of a City or Town, give name _____ (c) If outside corporate limits of a City or Town, check here _____			
2. GIVE MAKE _____ AND YEAR MODEL _____ OF VEHICLE YOU NOW OPERATE.			
3. DID YOU PURCHASE THIS VEHICLE NEW? _____			
4. PRESENT SPEEDOMETER READING _____ MILES			
5. GIVE MILES ABOVE VEHICLE WAS DRIVEN DURING 1937; OR IF YOU CHANGED VEHICLES DURING 1937 GIVE COMBINED TRAVEL FOR BOTH VEHICLES: (a) Total miles traveled regardless of States _____ (b) Total miles traveled in Georgia _____			
6. AVERAGE NUMBER OF MILES OBTAINED PER GALLON OF GASOLINE _____			
7. ARE THE ANSWERS TO QUESTIONS 5 AND 6 BASED ON: Estimates _____ or Records _____ (Check one)			
8. SHOW: \$ _____ and _____ Maintenance Tag Fee Paid Factory Weight			
9. IS THIS VEHICLE OPERATED FOR HIRE? _____			
10. WHAT IS YOUR OCCUPATION? _____			

Form HPS-326

PART VI

ROAD LIFE STUDY

Road Life Study

The purpose of a Road Life Study is to determine the average service life, rates of retirement, and annual roadway cost for each type of surfacing on all roads included in the State primary system. Life tables and curves, similar to birth, death, and population tables for human beings, will be developed from a year by year study of construction and retirement in order to determine the probable average service life and rates of retirement. Annual roadway cost will then be determined from a combined study of the average service life, construction and maintenance cost and probable salvage value.

Definitions:

Road surface is any roadway surface material other than natural earth.

Road surface life is the number of years that a section of surface is actually used before being abandoned or changed by reconstruction.

Road surface retirement or death is the removal from service of any section of road surface.

Road surface transfer is continuation of service as part of another road or street system.

Highway maintenance is the preservation of each type of roadway, structure, and facility as nearly as possible in its original condition of construction. General maintenance does not include reconstruction, resurfacing, widening, or any addition or betterment.

Salvage value is the percentage of original cost utilized in the reconstructed roadway.

Dual type pavement is one with a surface consisting of two or more types.

The Road Life Study may be broken down into three main divisions as follows:

1. Construction and retirement mileage by each separate construction contract
2. Cost of construction of each contract
3. Cost of maintenance and betterment by road sections

Information compiled in the first two divisions shall be tabulated on Form RL-1 (see sample form), and that in the last division on Form RL-2 (see sample form). The source of information shall be the records of the State Highway Department.

Form RL-1

Information shall be tabulated on Form RL-1 (see sample form), according to the following general descriptions:

Section 1:

Surface: Show cross sectional thickness and describe in detail the wearing course, using the same classification as listed under Road Inventory. If the surface is bituminous, the number of applications or courses shall be stated, whether a hot or cold mix was applied, and whether the method of preparation was by stationary or traveling plant or road mix.

Base and Foundation: Show cross section of base material and foundation and describe the type of each. The base shall be considered as any prepared course directly beneath the wearing surface and the foundation as the prepared course between the base and the natural earth sub-

grade.

Subgrade: Indicate the type and kind of treatment given to the subgrade.

Seal: Give description of the seal coat and indicate the amount and kind of bitumen and sand or pea stone used.

Bitumen: Give the amount and kind of oil, tar, asphalt or other bituminous material used.

Portland Cement: State whether the portland cement used was standard portland, high strength, high-early strength, or other special type, and give brands. If calcium chloride was added to the mix, this shall be noted.

Fine Aggregate: Describe the kind, source, and grading of the fine aggregate used in concrete and bituminous mixes.

Coarse Aggregate: Use same procedure as for fine aggregate.

Proportioning: State whether the method of proportioning the mix was by weight, volume, or design, and indicate what proportion was used.

Curing: Show whether curing was done by burlap, earth, ponding, calcium chloride, or other means and note length of curing time.

Strength of Concrete: Give average strength and age of concrete cylinders or beams at the time of construction and the strength of cores at a later date as determined by tests.

Pavement Steel: Describe the steel used in the pavement as to size, kind, type, and placement spacing.

Contraction and Expansion Joints: Give kind and placement spacing of expansion joints and indicate type of joint filler used whether sealing was from subgrade.

Longitudinal Center Joints: Show type, size, and spacing of steel for longitudinal center joint.

Shoulders: Note width of shoulder and the type, whether earth, gravel, or bituminous.

Right-of-Way: Give width of the right-of-way, indicating the length of various widths.

Section 2:

Bridges: All bridges, with spans of twenty feet or more in length, shall be described. Bridges constructed under separate contract shall be listed on separate sheets.

Section 3:

Construction Costs: Show total cost including contract payments, force accounts, state-furnished materials, and other. Additional items such as roadside development, traffic signs and markers, guard rails, and administration may be separated.

Section 4:

Describe the construction location by survey stations or mile post at the beginning and end of the project, also by termini, such as state and county lines, city limits, and route intersections.

Section 5:

This section is self-explanatory.

Section 6:

List each retirement resulting from each improvement, indicating the reason for and the method of retirement, and the type of replacement as follows:

Reason for Retirement:

1. Unclassified

2. Surface, base, and structural failures
3. Failure of surface
4. Failure of base
5. Failure of foundation or subgrade
6. Obsolescence
7. Relocation of curves and alignment
8. Grade reductions
9. Change to another or same type to meet traffic demands as to capacity, speed, and load
10. Combination of surface and structural failures and change to another or same type to meet traffic demands
11. Related highway improvements
12. Widening operations
13. Grade separations
14. Bridges and drainage structures
15. Intersections, cross-overs, and traffic circles
16. Public and private construction of dams, reservoirs, canals, sewers, and buildings
17. Catastrophes
18. Transfer by relocation of roads to another public authority which will continue the road in use.

Method of Retirement:

1. Torn up, no attempt at salvage
2. Used as a base for new surface
3. Used as a foundation for new pavement
4. Abandoned in place, not to be used further
5. Returned to another authority and continued as a public highway

c

Type of Replacement:

1. New construction
2. Resurfacing, same type
3. Resurfacing, different type
4. Replacement by new surface and new base, same or different type and same or greater width; old surface not saved
5. Change in alignment, vertical and horizontal
6. Widening, only when existing surface remains in use
7. Grade crossing
8. Bridge construction

Section 7:

Describe any unusual features under remarks.

Section 8: (Reverse side)

Separate contract costs and payments according to their specific divisions.

Section 9:

Indicate any unusual costs or payments under remarks.

Form RL-2

A separate study should be made of general maintenance cost, the cost of additions and betterments, and the cost of reconditioning. The study should cover as many years of the immediate past as there are suitable records available. The total cost of each operation shall include all direct and indirect charges, such as labor, consumable supplies, road equipment charges, direct overhead and supervision, and administrative costs. Detours shall be scheduled as a separate operation or as a temporary maintenance section.

All pertinent information shall be tabulated on Form RL-2

(see sample form), according to the following classifications:

Section 1:

Give detailed description of the maintenance section under investigation.

Section 2:

Describe each construction section embraced by the maintenance section being studied.

Section 3:

Tabulate by each year the average twenty-four hour density count for passenger cars, trucks and busses, and total traffic moving over each section.

Maintenance costs for all items numbered from 100 to 160, inclusive, shall be separated as to routine work and periodic work as follows:

Routine Work:

1. Patching holes, rough spots, ruts, blow-ups, and raveled edges; cleaning and clearing surface
2. Filling and trimming expansion joints and cracks
3. Sanding bleeding spots and spot sealing
4. Dragging, blading, reshaping, and scarifying
5. Repairing and maintaining the base, foundation and subgrade, and removing ledge rock
6. Mud jacking
7. Towing vehicles through mud holes and laying and removing temporary traffic ways

Periodic Work:

1. Applying dust palliatives
2. Replacing sand, gravel, crushed stone, chert and other loose surfaces with the same or similar

material to thickness of less than one inch

3. Reconditioning bituminous mats with the addition of little or no new oil or gravel
4. Treating bituminous surfaces, seal coating, and applying light road mixes to a thickness of three quarters of an inch or less in one operation

Shoulder and side approach costs (item 170) include:

1. Patching, dragging, blading, filling ruts and washouts
2. Replacing earth, gravel, and other shoulder materials
3. Reseeding and resodding shoulders
4. Bituminous treating without excavation

Drainage and roadside costs (items 180 and 190) embrace the following charges:

1. Repairing cuts, fills, back slopes, washouts, land slides, and bank protection
2. Cleaning and retrenching open drains, channels and ditches, and cleaning culverts
3. Removing wrecks, debris, fallen trees and advertising signs, and moving and repairing fences
4. Cutting and eradicating weeds, clearing brush, trimming trees, planting and sodding to prevent erosion

Drainage structures (item 200), with a span of less than twenty feet, shall include charges for:

1. Repairing
2. Repainting
3. Reflooring

Bridges and viaducts (item 210), with a span of over

twenty feet and under one hundred feet, shall include the same costs as for drainage structures (item 200). Structures with a span of over one hundred feet shall be considered as a separate maintenance section.

Roadside development costs (item 220) shall include:

1. Replacing trees and shrubs
2. Trimming trees and shrubs
3. Mowing
4. Watering
5. Fertilizing
6. Lighting

Snow and ice control charges (item 230) embrace the following:

1. Installing snow fences
2. Removing snow fences
3. Removing snow and ice
4. Sanding icy surfaces

Traffic service costs (item 240) include:

1. Repairing and painting markers, signals, and gates
2. Painting guide lines
3. Repairing and painting guard rail
4. Lighting the highway and operating signals
5. Operating comfort stations and picnic grounds
6. Directing traffic temporarily during floods or wash-outs and periods of congestion

Miscellaneous structure charges (item 250) include the cost of repairing and maintaining the following structures:

1. Sidewalks
2. Dykes

3. Retaining walls
4. Rip-rap
5. Pumping stations

Extraordinary maintenance costs (item 360), incurred by floods, storms, fires, and earthquakes, include:

1. Repairing the surface
2. Repairing the shoulders
3. Repairing the roadside
4. Repairing the structures
5. Dynamiting ice to protect bridges

Non-maintenance administrative, engineering and other functional charges (item 270) cover the cost of the following:

1. Traffic counts
2. Operating pit scales
3. Crack and condition surveys
4. Logging route mileage
5. Right-of-way project and section markers

Section 4: (Reverse side)

Addition and betterment costs shall be segregated from general maintenance costs, and shall be separated as to charges incurred by the various items listed under this section.

Surface, base, foundation and subgrade costs (items 10 and 20) shall include:

1. Widening curves, surfaced width, or intersections
2. First seal coat, if added within ninety days after construction
3. Building new curb
4. Filling expansion joints left open on construction

5. Frost boil prevention work

6. Additional sub-surface drainage

Shoulder and side approach costs (item 30) embrace the following charges:

1. First graveling of earth shoulders, approaches and turnouts
2. First bituminous treatment of plain surfaced shoulders
3. First bituminous ribbons along edge of pavement when shoulders are excavated and gravel added
4. Building approaches and farm entrances
5. Widening shoulders

Drainage and roadside costs (items 40 and 50) include:

1. Purchase of additional right-of-way for curve widening
2. Erecting permanent snow fences or planting permanent snow screens
3. Building fences
4. Raising, lowering or widening grade
5. Widening cuts
6. Back sloping

Drainage structure expenditures (item 60) include:

1. Extending old culverts
2. Building new culverts
3. Building new wing walls to old or new drainage structures

Roadside development charges (item 70) cover the cost of original landscaping projects.

Traffic service costs (item 80) embrace the following

items:

1. Original installation of traffic controls, markers, and safety signs
2. Constructing traffic circles
3. Installing original or additional guard rail
4. Constructing comfort stations, picnic grounds, and roads to scenic or historical points

Miscellaneous structure costs (item 90) include:

1. Constructing new retaining walls
2. Building revetments
3. Installing rip-rap
4. Constructing channel changes

Section 5:

This section is self-explanatory.

Section 6:

The length and termini of each maintenance section and the portion upon which work was performed shall be indicated by the year.

8. CONTRACT COSTS AND PAYMENTS

Contract Price			Payments By		
Additions			Fed. Government		
Extras and Credits			State		
Force Account			County		
Total			City		
Deductions			R.R. Company		
Net Payment					
State furnished Material					
Net Total Cost					

9. REMARKS

(Over)

STATE HIGHWAY DEPARTMENT

MAINTENANCE COST STUDY

1. MAINTENANCE SECTION

Division No.		Proj. Class					
County		Proj. No.					
Route No.		Proj. Sec.					
Maint. Sec.		Contract No.					
Year Built		Date Comp.					
Surface Type		Surface Type					
Width		Width					
Miles		Miles					
		X-Sec.					

3. GENERAL MAINTENANCE COSTS (NEAREST DOLLAR)

[illegible]

Form RL-2 (Reverse Side)

4. COST OF ADDITIONS AND BETTERMENTS

Item	1928	1929	1930	1931	1932	1933	1934	1935
10 Surface & base								
20 Roadbed (subgrade)								
30 Shoulders & approaches								
40 Right-of-way								
50 Fills, cuts, open drng.								
60 Drainage structures								
70 Roadside development								
80 Traffic services								
90 Misc. structures								
TOTAL								

5. GRAVEL RESURFACING, RECOILING, RECONDITIONING & SEALING RECORD

5a. Materials and Cost Record

Item	19	19	19	19	19	19
Length resurf. or recond.						
Total cu. yds. aggregate						
Cu. yds. aggregate per mile						
Total gals. oil						
Gals. oil per mile						
Kind & size aggregate						
Kind of oil						
Nature of work						
Total cost of work						
Cost per mile						

5b. Length & termini of Maintenance Section & Portion Worked Upon

19__	<div></div>
19__	<div></div>
19__	<div></div>
19__	<div></div>
19__	<div></div>
19__	<div></div>

0

5

10

15

20

25

30



Railroad Grade Crossing

View Over Crossing Completely Restricted

PART VII

SUMMARY

Summary

A multitude of situations have arisen as a result of extended highway improvements. The burden of capital investment and maintenance placed upon the users as a whole through the medium of taxes and imposts bears no direct relationship between the users of roads and the type of operation as in the case of urban and rural residents and of commercial and private operations. There has been no generally scientific determination of amounts that should be charged against users of roads under each jurisdiction, nor has there been any accurate application of this principle of user payment.

The state highways, representing about 10 to 12 per cent of the rural mileage and 35 to 37 per cent of use, in recent years received 77 per cent of special taxes and fees. Other rural roads, representing 88 to 90 per cent of the total rural mileage and 16 to 17 per cent of use, received 17 per cent of special taxes and fees. City streets, representing 260,000 miles and 45 to 50 per cent of use, received 6 per cent of special taxes and fees.


The lack of sufficient and accurate information in the past has greatly impeded intelligent planning and we know that mistakes have been made in promoting or restricting improvements. Highway improvements have been made separately and independently of other forms of transportation, in some cases duplicating these other agencies. They have been made under the aegis of social and political purposes, but have been permitted to be used for commercial purposes without regulatory supervision, resulting in unfair distribution of cost to the non-commercial


users. Improvements have been made prior to the collection of funds so that the general public is ultimately mortgaged to assure payment. They have been made project by project, under different jurisdictions, but are being used generally by vehicles from many jurisdictions so that fees, taxes and imposts have been expended without due regard to individual improvement. In many instances, these improvements have never been designed, as a private undertaking must be designed, with consistent relation to the carrying facility of highways either as to alignment, grade, width, strength, or surfacing, nor as to safety of railroad crossings and the strength and width of bridges.


Application of the data compiled by the Highway Planning Survey will prove of inestimable value for future planning of highway improvements. The road inventory will provide us with definite information regarding the extent, type and condition of our entire highway system; the traffic survey will indicate the amount and nature of traffic over the various types of roads; the financial survey will permit us to analyze past and future distribution of public taxes with respect to highway expenditures; and finally the road life study will enable us to determine the life expectancy of the various types of roads and to design such roads as are best suited to their own particular purpose.

We must not lose sight of the fact, however, that improvement of our entire highway system is bound up implicitly with the technical advancement of the automotive industry and with the increase of motor vehicle transportation. Therefore, the data secured by this survey must be supplemented by additional information at specified intervals in order to keep the data currently

up to date. If we do not keep our information up to date, we will be as improvident as the man who designs and erects a beautiful and substantial structure and then permits it to deteriorate through lack of proper protection and maintenance.





 HIS MAP is presented to you by the State Highway Board of Georgia with the hope that it will help to guide you over our vast system of State highways and will suggest, not only to guest motorists but also to our own residents, a few of the points of interest within our State well worth seeing.

There are many points and towns of historic interest and scenic beauty in Georgia, but space permits us to show only a few on the Scenic Map, with some of the important highway connections to show that they may be reached easily. We feel that a visit to any of these will stimulate your interest sufficiently to visit others not shown, but of equal importance and beauty throughout the State.

There is no season of the year when Georgia highways will not lead you through beautiful scenes. The mountain grandeur of our northern section, the beautiful central and southern portions, and the coast, with its rich historic traditions and "old southern" atmosphere, all beckon to the traveler. There is not a single section which cannot be reached over smooth and well-marked highways.

The State Highway Board and the people of Georgia invite the motorists of America to visit the Empire State of the South and enjoy its scenic beauty and true southern hospitality.

Copies of this map may be obtained upon application to the State Highway Board of Georgia, 2 Capitol Square, Atlanta; any Chamber of Commerce in the State or any local newspaper in towns in which there is no Chamber of Commerce.

Current detour information may be obtained upon application to the State Highway Board, Atlanta, or the Division offices of the State Highway Department, located at Augusta, Columbus, Fitzgerald, Gainesville, Macon, Rome and Savannah.

COMMERCIAL AND EMERGENCY AIRPORTS

NOTE: Mileage is from center of city

ADAIRSVILLE—E. of US 41 (State 3); 1.5 mi. N.	JACKSON—S.W.
ALBANY—W. of State 19; 1.5 mi. S.W.	JEFFERSON—S. of US 124 (State 15); 1.8 mi. S.
ALMA—S. of State 27; 1.5 mi. S.W.	LODRIDGE—CALAVERA FLD., E. of State 14; 1 mi. S.W.
AMERICUS—1.5 mi. S.	LAYONIA—E. of State 58; 2 mi. S.; 2 mi. S.W.
ATHENS—EPHS FIELD, N. of State 10; 4 mi. N.E.	MACDON—HERBERT SMART FIELD, E. of State 87; 5.5 mi. S.E.
ATLANTA—CANDLER FIELD, N. of State 19 (State 3) and US 29 (State 14); 9.5 mi. S.W., from new P.O.	MADISON—E. of State 83; 2 mi. S.W.
AUGUSTA—DANIEL FIELD, S. of Water Works; W. of U. S. Government Hospital; 5.1 mi. S.W.	MARAS—E. of State 27; 1.9 mi. S.
BAINBRIDGE—COMMOODORE DECATUR AIRPORT, W. of US 84 (State 1); 2 mi. W.	MARTINVILLE—CASE FOWLER AIRPORT, W. of State 24; 1.9 mi. N.W.
BRUNSWICK—GLYNN COUNTY AIRPORT, 6 mi. E. on St. Simon	MCQUEET—CLARK FIELD, 1 mi. N.W.
BUENA VISTA—At intersection of State 28 and 47; 1.3 mi. N. by N. 28	MYRTLE—N.W.
CARTERSVILLE—E. of State 20; 2.5 mi. N.E.	ROYSTON—E. of State 17; 1 mi. N.
COCHRAN—S. of State 24; 2 mi. E.	SAINT MARYS—1.5 mi. N.W.
COLUMBUS—S. of US 27 (State 1); 23 mi. S.E.	SAVANNAH—HUNTER FIELD, E. of State 24; 6 mi. S.
CORDELE—22 mi. W. of US 41 (State 7); 2 mi. N.W.	STATESBORO—E. of State 73; 3.7 mi. N.
DALTON—E. of US 15 (State 4); 2 mi. N.W.	SWAINSBORO—E. of US 15 (State 4); 1.5 mi. S.E.
DOUGLAS—W. of State 31; 1.5 mi. S.	TALPOOSA—10 mi. S.W. of Bremen.
ELBERTON—E. of State 34, E. of State 17; 2.5 mi. S.E.	THOMASTON—W. of US 19 (State 3); 2 mi. N.
ELIZABETH—LYNNWOOD AIRPORT, N. of County (Hill) Rd.; 1.8 mi. N.	THOMASVILLE—VESE FIELD, E. of State 31; 1.2 mi. S.W.
FOLKSTON—W. of US 1 (State 4); 1.8 mi. N.W.	TUSTON—W. of US 41 (State 7); 3.5 mi. S.
FORT BENNING—On Chattahoochee River, W. of headquarters.	VALDOSTA—W. of US 41 (State 17); 3.8 mi. S.
GAINESVILLE—E. of County Rte. 3, mi. S.E.	WARM SPRINGS—ROOSEVELT FIELD, E. of State 41; 2.5 mi. N.
GRAFFIN—W. of State 3; 1.8 mi. S.	WAYCROSS—WACE COUNTY AIRPORT, W. of US 1 (State 4); 3.5 mi. W.
	WINDER—RUSSELL FIELD, 1 mi. N.E.

Typical Scenes Along Georgia Highways



This chart shows the distance between some of the principal points in Georgia; also distances between these points and several important cities in other States. Distances are based upon mileage from center of corporation to center of corporation via the shortest practicable route. For distances between points, other than those shown on this chart, see map on reverse side.

HOW TO USE CHART. The mileage between any two points is shown at the intersection of the horizontal line leading from left to right from one of the points, with the vertical line leading downward from the other. For instance, to find the distance from Albany to Atlanta, follow the line leading to the right from Albany until it intersects the line leading to Atlanta. The figure in the square is 169 which is the mileage between the two points.

[illegible]

STATE HIGHWAY BOARD
OF
GEORGIA

W. L. MILLER
CHAIRMAN

JIM L. GILLIS
MEMBER

HERMAN H. WATSON
MEMBER

E. A. STANLEY
STATE HIGHWAY ENGINEER

O. T. RAY
DIRECTOR, DIVISION OF HIGHWAY PLANNING



STATE HIGHWAY BOARD OF GEORGIA BUILDING
TWO CAPITOL SQUARE, ATLANTA, GA.

1938
FOR FREE DISTRIBUTION

OFFICIAL MAP
STATE HIGHWAY SYSTEM
OF
GEORGIA



E. D. RIVERS

Governor

1938

FOR FREE DISTRIBUTION

STATE OF GEORGIA

SYSTEM OF STATE ROADS

Prepared By
STATE HIGHWAY BOARD OF GEORGIA

DIVISION OF HIGHWAY PLANNING

Scale of Miles

APPROVED:
[Signature]
STATE HIGHWAY ENGINEER

APPROVED BY THE STATE HIGHWAY BOARD IN REGULAR SESSION,
JANUARY 15, 1938
[Signature]
FORWARD: H. H. HARRIS

Legend

- COMPLETED HARD SURFACE
- COMPLETED SEMI-HARD SURFACE
- BAND CLAY OR TOP SOIL
- COMPLETED GRADING NOT SURFACED
- UNDER CONSTRUCTION - ALL TYPES
- UNIMPROVED BUT MAINTAINED
- BRIDGE UNDER CONSTRUCTION
- COMPLETED BRIDGE
- STATE ROUTE NUMBER
- U.S. INTERSTATE ROUTE NUMBER
- MILEAGE BETWEEN POINTS
- STATE CAPITAL
- COUNTY SEAT
- JUNCTION POINT
- AIRPORT
- RED CROSS FIRST AID STATION
- COUNTY BOUNDARIES
- PARKS
- NATIONAL FOREST AREA



ATLANTIC OCEAN

JACKSONVILLE

FLORIDA